

1 LOCATION OF WATER WELL: County: CLAY	Fraction SE 1/4 SE 1/4 SE 1/4	Section Number 26	Township Number T 7 S	Range Number R 2 EW
--	---	-----------------------------	---------------------------------	-------------------------------

Distance and direction from nearest town or city street address of well if located within city?

3 south, 1 east, 2 south of Morganville, KS

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP Code :	Bob Weitharn 1919 Kiowa Rd. Clay Center, KS 67432	Drilled 05/05/98	Board of Agriculture, Division of Water Resources Application Number:
---	--	-------------------------	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL... 60' ft. ELEVATION:
--	--

Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL . **25' - 8 1/2"** ft. below land surface measured on mo/day/yr **05/12/98**

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield **450** gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter . **24"** in. to ft., and in. to ft.

WELL WATER TO BE USED AS:

5 Public water supply	8 Air conditioning	11 Injection well
1 Domestic	3 Feedlot	6 Oil field water supply
2 Irrigation	4 Industrial	7 Lawn and garden only
9 Dewatering	12 Other (Specify below)	

Was a chemical/bacteriological sample submitted to Department? Yes.....No **X**.....; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes **X** No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	11 None used (open hole)

Blank casing diameter . **16"** in. to **0-40** ft., Dia in. to ft., Dia in. to ft.

Casing height above land surface . **24"** in., weight **1554** lbs./ft. Wall thickness or gauge No. **.500**

TYPE OF SCREEN OR PERFORATION MATERIAL: .080 slot		7 PVC	10 Asbestos-cement
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped	8 Saw cut
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS:		11 None (open hole)	

GRAVEL PACK INTERVALS: From **40** ft. to **60** ft., From ft. to ft.

From ft. to ft., From ft. to ft.

From **30** ft. to **60** ft., From ft. to ft.

From ft. to ft., From ft. to ft.

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
-------------------	---------------	----------------	-------------	---------------

Grout Intervals: From **6** ft. to **30** ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	

Direction from well? How many feet? **None within 1/4 mile**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	21	Clay-Brown-Silty			
21	24	FS-Cs-Med Gravel-Brown			
24	33	FS-CS-Med Gravel Pea-Brown			
33	37	FS-Cs-Med Gravel Pea-Brown 1/4"			
37	39	FS-Cs-Med Gravel-Brown			
39	45	FS-Cs-Med Pea 1/4x3/8-Green-Blue			
45	53	FS-Cs-Med Pea 1/4"			
53	60	FS-CS-Med Pea Green			
60	64	Clay-Grey			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 05/12/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 182 This Water Well Record was completed on (mo/day/yr) 6-3-98 under the business name of STRADER DRILLING CO., INC. by (signature) <i>Dale Ashen</i>
--

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY