

74

VBRT

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215


Kansas Department of Health and Environment
Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

dba filed

1. Location of well: County Tackson Fraction SE 1/4 NE 1/4 NW 1/4 SE 1/4 Section number 18 Township number T 8 R 15 E NW Range number 15

2. Distance and direction from nearest town or city: 1/2 N + 3 W 3. Owner of well: JACKSON COUNTY
Street address of well location if in city: Mayetta, Kans. R.R. or street: Courthouse
City, state, zip code: Holtan, KS 66436

4. Locate with "X" in section below: Sketch map: Well "B"
Observation Hole for
Jackson Co. Landfill



7. Bore hole dia. 8 in. Completion date 12-2-77
Well depth 30 ft.

8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other

9. Casing: Material PVC Height: (Above) or below
Threaded Welded Surface 24 in.
RMP PVC Glue Weight 2.75 lbs./ft.
Dia. 5 in. to 30 ft. depth Wall Thickness: inches or
Dia. in. to ft. depth gage No. 258

5. Type and color of material	From	To
<u>Brown Clay</u>	<u>0</u>	<u>8</u>
<u>Grey Shale</u>	<u>8</u>	<u>25</u>
<u>Grey Shaley Limestone</u>	<u>25</u>	<u>26</u>
<u>Red Shale</u>	<u>26</u>	<u>28</u>
<u>Grey Shale</u>	<u>28</u>	<u>30</u>

10. Screen: Manufacturer's name MPE
Pumpco
Type PVC Dia. 5"
Slot gauze .020 Length 20'
Set between 10 ft. and 30 ft.
ft. and ft.
Gravel pack? Size range of material .030x.060

11. Static water level: NONE mo./day/yr.
ft. below land surface Date 12-2-77

12. Pumping level below land surfaces:
ft. after hrs. pumping g.p.m.
ft. after hrs. pumping g.p.m.
Estimated maximum yield 0 g.p.m.

13. Water sample submitted: mo./day/yr.
Yes No Date 12-2-77

14. Well head completion: Capped
Pitless adapter 24 inches above grade

15. Well grouted?
With: Neat cement Bentonite Concrete
Depth: From 0 ft. to 10 ft.

16. Nearest source of possible contamination:
ft. 30 Direction N Type Ditch
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name _____
Model number _____ HP _____ Volts _____
Length of drop pipe _____ ft. capacity _____ g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation: 1140
Topography: Hill
 Slope
 Upland
 Valley

19. Remarks: Aquifer Made NO WATER
Sampling well

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
STRAKER DRIG. CO INC 182
Business name License No. _____
Address RT 1 Holtan, KS
Signed Dale Graham Date 12-5-77
Authorized representative

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

BR=1132
I = 1132