


USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | | | | | |
|---|--|--------------------------------------|--|--|-----------|--|--|---|--|
| 1. Location of well: County CLAY | | Fraction NW 1/4 SW 1/4 SW 1/4 | | Section number 14 | | Township number T 8 S R 2 | | Range number 2 E/W | |
| 2. Distance and direction from nearest town or city: 1 SOUTH 2 3/4 WEST Street address of well location if in city: CLAY CENTER | | | | 3. Owner of well: MYRON WOHLER R.R. or street: RT #5 City, state, zip code: CLAY CENTER, KANS 67432 | | | | | |
| 4. Locate with "X" in section below:  | | | | Sketch map: | | 6. Bore hole dia. 8 in. Completion date 3/7/77 Well depth 60 ft. | | | |
| | | | | | | 7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary | | | |
| | | | | | | 8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | | | |
| | | | | | | 9. Casing: Material PVC Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight 3 lbs./ft. Dia. 5 in. to 60 ft. depth Well Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 1258 | | | |
| 5. Type and color of material | | | | From | To | 10. Screen: Manufacturer's name PUMPCO Type PVC Dia. 5" Slot/gauze 1/16 Length 20' Set between 40 ft. and 60 ft. ft. and <input type="checkbox"/> ft. Gravel pack? YES Size range of material 1/4" x 1/4" | | | |
| TOPSOIL | | | | 0 | 3 | 11. Static water level: <input type="checkbox"/> mo./day/yr. 30 ft. below land surface Date 3/7/77 | | | |
| BROWN CLAY | | | | 3 | 23 | 12. Pumping level below land surface: <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. <input type="checkbox"/> ft. after 15 hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 30 g.p.m. | | | |
| GRAVEL | | | | 23 | 33 | 13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> | | | |
| BROWN CLAY | | | | 33 | 36 | 14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter 12 inches above grade | | | |
| GRAVEL | | | | 36 | 42 | 15. Well grouted? YES With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 3 ft. to 13 ft. | | | |
| LIMESTONE | | | | 42 | 58 | 16. Nearest source of possible contamination: HOG 500 ft. Direction EAST Type SHED Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | | | |
| BLUE CLAY | | | | 58 | 60 | 17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | | | |
| STOP | | | | 60 | | | | | |
| | | | | (Use a second sheet if needed) | | | | | |
| 18. Elevation: | | 19. Remarks: | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Geo Lox & Sons Inc 258 Business name License No. LLIFTON KANS 66937 Address CLAY CENTER, KANSAS Signed K. RAYL Date 3/7/77 Authorized representative | | | | | |
| Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | | | | | |

T
R
W
E
S
E
C
1/4
1/4
1/4
1/4
NW SW SW
258