



PROJECT: Tire Town Phase II		WELL / BORING NO: <b>MW-3</b>	
LOCATION: Leavenworth, Kansas			
STARTED: 9/28/04	COMPLETED: 9/28/04	TOC Elev:	Geologist: D.M.
DRILLING COMPANY: PSA ENVIRONMENTAL		Surface Elev:	Driller:
DRILLING EQUIPMENT:		Depth to GW:	Static GW Elev:
DRILLING METHOD: DIRECT PUSH			

DEPTH (ft)	GRAPHIC LOG	USCS	DESCRIPTION	SAMPLE	LAB SAMPLE	PID (ppm)	Recovery	WELL CONSTRUCTION
0	D		GRAVEL Sandy Silty CLAY; dark brown.			0	2.5	CONCRETE
5			Silty CLAY; brown; firm; moist; low plasticity.			0	4.2	BENTONITE
10			CLAY; light brown; firm; moist; low-med plasticity.			0	6	SAND PACK
15			CLAY; grayish-brown; firm; wet at 15 feet; low-med plasticity.			0		1" PVC SLOTTED SCREEN
20			SILT; greenish gray; soft; wet; with some very fine sand.			0	4.7	
20			Boring Terminated.					

LAEWINDA-4390183.GPJ LAEWINDA.GDT 8/1/05

721 S. Peckard  
 Kansas City, Kansas  
 Telephone: 913-321-8100  
 Fax: 913-321-8181

**Maxim Technologies Inc.**

PROJECT NO. 4390183