

52

elev. changed 1180 - 1093

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

bac 200

1. Location of well: County Jackson Fraction SW 1/4 NE 1/4 NW 1/4 Section number 31 Township number T 9 S R 16 Range number EW

2. Distance and direction from nearest town or city: 1 1/4 S 1 1/2 E 3. Owner of well: Herb Poort
Street address of well location if in city: Moyst R.R. or street: RR 1
City, state, zip code: Moyst, Kansas 66440

4. Locate with "X" in section below: Sketch map:

6. Bore hole dia. 8 in. Completion date 11-10-78
Well depth 120 ft.

7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other

9. Casing: Material PVC Height: 60 or below
Threaded Welded Surface 24 in.
RMP PVC 516E Weight 2.74 lbs./ft.
Dia. 5 in. to 120 ft. depth Wall Thickness: inches or
Dia. 5 in. to 120 ft. depth gage No. 258

10. Screen: Manufacturer's name Pumpco
Type PVC Dia. 5 1/4
Slot/gauze 080 Length 40
Set between 80 ft. and 120 ft.
Gravel pack? Yes Size range of material 1/4 X 1/8

11. Static water level: 70 ft. below land surface Date 11-10-78

12. Pumping level below land surfaces: Pin Test
 ft. after hrs. pumping g.p.m.
 ft. after hrs. pumping g.p.m.
Estimated maximum yield 5 g.p.m.

13. Water sample submitted: mo./day/yr.
 Yes No Date

14. Well head completion: Top Cap
 Pitless adapter 24 inches above grade

15. Well grouted? Yes
With: Neat cement Bentonite Concrete
Depth: From 0 ft. to 10 ft.

16. Nearest source of possible contamination: 100 ft. Direction N Type Lateral S
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name
Model number HP Volts
Length of drop pipe ft. capacity g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

5. Type and color of material	From	To
Top Soil	0	4
Yellow Shale	4	10
Gray Shale	10	17
Gray Limestone	17	21
Gray Shale	21	22
Lt. Gray Limestone (Shaley)	22	32
Gray Shale	32	37
Lt. Gray Shaley Limestone	37	43
Gray Shale	43	105
Gray Sandy Shale	105	108
Gray Sandstone	108	115
White Sandstone	115	120

18. Elevation: 1050 rem
Topography: Hill Slope Upland Valley

19. Remarks: Owner to install Slab

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Business name STRADER Dalg Co License No. 182
Address RT 1 Holton, KS
Signed Dale Robinson Date 11-13-78
Authorized representative

T 9 S R 16 E W 31 SW NE NW 1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5