

Sent to Leonard
1/16/78

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County LEAVENWORTH	Fraction NE NE 1/4 SW 1/4 SE 1/4	Section number 87	Township number T 9 S	Range number R 23 E
2. Distance and direction from nearest town or city: 1 1/2 mi. S.E.			3. Owner of well: CITY OF LEAVENWORTH			
Street address of well location if in city:			R.R. or street: City, state, zip code: LEAVENWORTH, KS			
4. Locate with "X" in section below:			Sketch map:		6. Bore hole dia. 54 in. Completion date 9-8-77 Well depth 69 ft.	
					7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
5. Type and color of material			From		To	
TOPSOIL BROWN SILTY CLAY BROWN SILT GRAY SILTY SAND GRAY FINE TO VERY FINE SAND GRAY MEDIUM TO FINE SAND GRAY FINE TO VERY FINE SAND GRAY MEDIUM TO COARSE SAND w/TR GRAVEL			0 1 5 10 15 26 40 46 69		9. Casing: Material STEEL Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 16' RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 136.2 lbs./ft. Dia. 26 in. to 49 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. .500"	
					10. Screen: Manufacturer's name LAYNE	
					Type SHUTTER Dia. 26"	
					Slot/gouze .105" Length 20'	
					Set between 49 ft. and 69 ft.	
					Gravel pack? YES Size range of material .26"	
					11. Static water level: 12 ft. below land surface Date 10-13-77	
					12. Pumping level below land surfaces: 21.3 ft. after 4 hrs. pumping 1050 g.p.m. 21.3 ft. after 8 hrs. pumping 1050 g.p.m. Estimated maximum yield 2000 g.p.m.	
					13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 11-14-77	
					14. Well head completion: 16' inches above grade	
					15. Well grouted? YES	
					With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete	
					Depth: From 0 ft. to 20 ft.	
					16. Nearest source of possible contamination: ft. 300 Direction NORTH Type MO. RIVER Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
					17. Pump: <input type="checkbox"/> Not installed	
					Manufacturer's name LAYNE & BOWLER	
					Model number 11" BHC HP 60 Volts 460	
					Length of drop pipe 10.3 ft. capacity 200 g.p.m.	
					Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine	
					<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
					<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
18. Elevation: 760			19. Remarks: WELL #5 & #5 Two loggers labelled 5		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. LAYNE-WESTERN 199 Business name License No. Address 1010 W. 39 Signed Dal G. Rye Date 1-11-78 Authorized representative	