

Star West Well

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

23

1. Location of well:		County Leavenworth	Fraction NW 1/4 SE 1/4 NW 1/4	Section number 33	Township number T 9 S R	Range number 23
2. Distance and direction from nearest town or city: Street address of well location if in city:		1/2 mile east of Lansing city limits		3. Owner of well: R.R. or street: City, state, zip code:		
					Mr. Paul Serwon 12373 Merion Drive Kansas City, Kansas	
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 8 in. Completion date 3-19-76 Well depth 140 ft.		
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Well #2 (West)				9. Casing: Material PL Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 18 in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 5 in. to 140 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 258WT		
Top Soil		0	3	10. Screen: Manufacturer's name Vinylplex, Inc. Type PVC Dia. <input type="checkbox"/> Slot/gauze .06 1/16 Length <input type="checkbox"/> Set between 20 ft. and 30 ft. 120 ft. and 130 ft. Gravel pack? <input checked="" type="checkbox"/> Yes Size range of material 1/4 - 1/8		
Brown Clay		3	22	11. Static water level: 22 ft. below land surface Date 3-19-76 mo./day/yr.		
Coarse Sand - Medium Gravel		22	23	12. Pumping level below land surfaces: <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1 g.p.m.		
Shale - Grey		23	88	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
Lime - Brown		88	100	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter 18 inches above grade		
Shale - Grey		100	120	15. Well grouted? <input checked="" type="checkbox"/> Yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 3 ft. to 23 ft.		
Lime - Grey		120	135	16. Nearest source of possible contamination: ft. 500' Direction North Type Septic Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Shale - Grey		135	140	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Jacuzzi Model number 5547A HP 1/2 Volts 220 Length of drop pipe 135 ft. capacity 10 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
		(Use a second sheet if needed)		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BREUER, INC. 174		
18. Elevation: 777 ft. Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks:		Business name Box 147 Basehor, Ks. 66007 Address Signed: [Signature] Date 3-20-76 Authorized Representative			