

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 820-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County: Riley		Fraction: SW 1/4 SW 1/4 SW 1/4		Section number: 14		Township number: T 9 S R		Range number: 7 G W			
2. Distance and direction from nearest town or city: 4 NW of				3. Owner of well: DUANE GILLIAM							
Street address of well location if in city: MANHATTAN				R.R. or street: City, state, zip code: RR6 MANHATTAN, Ks. 66502							
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile				Sketch map: DRAINAGE DITCH X well 150'				6. Bore hole dia. 8 in. Completion date: 11-6-78 Well depth 260 ft.			
								7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
								8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
								9. Casing: Material PVC Height Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 24 in. RMP <input type="checkbox"/> PVC 9L Weight 2150 lbs./ft. Dia. 5 in. to 260 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 1279			
5. Type and color of material				From		To		10. Screen: Manufacturer's name PUMPCO MPI Type PVC Dia. 5 <input checked="" type="checkbox"/> gauze .060 Length 100 Set between 160 ft. and 260 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/4 X 1/8			
TOP SOIL				0		2		11. Static water level: <input type="checkbox"/> mo./day/yr. 175 ft. below land surface Date 11-6-78			
Clay, BROWN				2		10		12. Pumping level below land surfaces: ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 6 g.p.m.			
Limestone, grey, shaley, lime, grey				10		83		13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> mo./day/yr.			
Shale, grey, yellow, Red				83		160		14. Well head completion: CAP <input type="checkbox"/> Pitless adapter 24 inches above grade			
Limestone, yellow, soft, broken				160		169		15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 5 ft. to 15 ft.			
Shaley Limestone, grey				169		203		16. Nearest source of possible contamination: ft. 150 Direction E Type DRAINAGE Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
shale, grey, Black, Red				203		225		17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
Shale, grey,				225		260		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. STRAIDER DAIG CO 182 Business name License No. Address RT1 Manhattan, KS Signed Dale Acker Date 11-8-78 Authorized representative			
(Use a second sheet if needed)											
18. Elevation: Topography: <input checked="" type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks: OWNER TO INSTALL SLAB									

T 9 S R 7 W 14 SW SW SW SW