

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.


GRINELL 11W

WATER WELL RECORD
KSA 82a-1201-1215

ADB ACB

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Thomas	Township name	Fraction SW-SE-NE SW-SE-NE	Section number 1	Town number 10 S	Range number 31 W
Distance and direction from nearest town or city:			3 Owner of well: Robert J. Ostmeyer			
Street address of well location if in city:			Address: RFD 1 Oakley, Ks. 67748			
Locate with "X" in section below: N  W S E 1 Mile			Sketch map:			
2 Type and color of material			From	To	4 Well depth: 212 ft. Date of completion 6-15-76 Well diameter 12 3/4 in.	
Topsoil, Clay silty, brown			0	30	5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Sandy clay, brown			30	110	6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well	
Sandy clay, trace sandstone, brown			110	128	7 Casing: Material steel Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. wall Diam. 12 3/4 in. to 199 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No _____ in. to _____ ft. depth	
Sandy clay, Med Gravel, brown			128	138	8 Screen: Manufacturer W. A. Brown Type Steel Slot Dia. 12 3/4 Slot/gauze 10/16 Length 20 Set between 199 ft. and 218 ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 5-14	
Sandstone, Trace Med Gravel, Sandy clay			138	148	9 Static water level: 116 ft. below land surface Date Apr 9 1976	
Sandstone, Trace Med Gravel, Trace Sandy clay			148	159	10 Pumping level below land surfaces: 208 ft. after 1 hrs. pumping 200 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 200 g.p.m.	
Sandy clay, Trace Med Gravel, Fine sand			159	163	11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
Sandy clay, brown, Streak Sandstone			163	179	12 Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade	
Sandy clay, brown, Trace Med Gravel brown			179	186	13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From 1 ft. to 10 ft.	
Med Gravel, Fine sand, brown			186	196	14 Nearest source of possible contamination: unknown ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Ochre yellow, Shale blue			196	218	15 Pump: <input type="checkbox"/> Not installed Manufacturer's name Pfizer PF1442 Model number _____ HP 40 Volts 260 Length of drop pipe 200 ft. capacity _____ g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(use a second sheet if needed)						
16 Remarks: elevation Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley 2980 (104)			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Red Tiger 125 Business name _____ License No. _____ Address 2016 1/2 Signed Joe P. ... Date 8-16-76 Authorized representative			