


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

BBB

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County <b>Thomas</b>	Township name <b>S. Randall</b>	Fraction <b>NW-NW-NW</b>	Section number <b>1</b>	Town number <b>10 S</b>	Range number <b>31 W</b>
Distance and direction from nearest town or city: <b>5 3/4 E, 6 N of Oakley, ks.</b>			3 Owner of well: <b>Bernard Huelsman</b> Address: <b>RFD 1 Oakley, Ks.</b>			
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:			
2			4 Well depth: <b>200</b> ft. Date of completion: <b>2-10-76</b> Well diameter: <b>28</b> in.			
Type and color of material			5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary			
From			6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well			
To			7 Casing: Material <b>steel</b> Height: <b>above</b> below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. Diam. <b>12 3/4</b> in. to <b>130</b> ft. depth Weight <b>5.16</b> lbs. <b>8165</b> Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
Topsoil, Clay, silty, brown			8 Screen: <b>W. A. Brown</b> Manufacturer <b>Steel</b> Dia. <b>12 3/4</b> Type <b>60/100 Fine No</b> Length <b>60'</b> Set between <b>130</b> ft. and <b>190</b> ft.			
Fine sand, Med Gravel, Streak Sandstone			Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <b>1/4"</b>			
Sandy clay, brown, Sandstone, white			9 Static water level: <b>119</b> ft. below land surface Date <b>2-10-76</b>			
Fine sand, Med Gravel, brown			10 Pumping level below land surfaces: <b>180</b> ft. after <b>8</b> hrs. pumping <b>500</b> g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield <b>500</b> g.p.m.			
Sandy clay, Fine sand, brown			11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date ____			
Fine sand, Med Gravel, Trace Sandy clay			12 Well head completion: <b>Casing</b> <input type="checkbox"/> Pitless adapter <b>None</b> <b>12</b> inches above grade			
Fine sand, Med Gravel, brown			13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> ____ Depth: From <b>1</b> ft. to <b>10</b> ft.			
Fine sand, Med Gravel, Trace Sandy clay			14 Nearest source of possible contamination: <b>Barn</b> ft. <b>500</b> Direction <b>NE</b> Type <b>yard</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
Fine sand, Med Gravel, Trace Sandstone			15 Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Goulds</b> Model number <b>40</b> HP <b>40</b> Volts ____ Length of drop pipe <b>180</b> ft. capacity <b>500</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
Sandstone, white, Fine sand, brown			16 Remarks: elevation  Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley			
Sandy clay, Trace Fine sand, Trace Sandstone			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Red Tiger Supply</b> <b>125-</b> Business name License No. Address <b>Box 504 Colby, KS</b> Signed <b>Les P</b> Date <b>2-14-76</b> Authorized representative			
Fine sand, Med Gravel, Trace Sandy Clay						
Ocher and Shale, yellow and blue						
BROCK 198'						
(use a second sheet if needed)						

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5