


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

AAC

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well:	County <b>Thomas</b>	Township name <b>SW-NE-NE</b>	Fraction	Section number <b>2</b>	Town number <b>10 S</b>	Range number <b>31 W</b>
Distance and direction from nearest town or city: <b>Approx 13 NE of Oakley</b>			3 Owner of well: <b>Edwin Huelsman</b> RFD 1 Oakley, Ks. 67748			
Street address of well location if in city:			Address:			
Locate with "X" in section below: 			Sketch map:			
2			Type and color of material		From	To
Top soil, Clay, silty, brown					0	30
Sandy clay, trace sandstone, Brown					30	60
Med Gravel, brown					60	72
Sandstone white, Sandy clay brown					72	120
Fine sand, Med Gravel, brown					120	132
Med Gravel, Sandy clay, brown					132	136
Med Gravel, Fine sand, browy					136	153
Sandstone, white, Sandy clay, brown					153	158
Med Gravel					158	165
Sandy clay, white rock, Med Gravel, stk					165	176
Sandy clay, brown					176	196
Med Gravel, brown					196	204
BROCK?						
(use a second sheet if needed)						
16 Remarks: elevation Concrete Slab installed before pump was set. Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley			4 Well depth: <b>204</b> ft. Date of completion <b>6-15-76</b> Well diameter <b>30</b> in. 5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary 6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/> 7 Casing: Material <b>Steel</b> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. <b>2011</b> Diam. Weight <b>219</b> lbs./ft. <b>123</b> in. to <b>194</b> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No in. to ft. depth 8 Screen: Manufacturer <b>W. A. Brown</b> Type <b>Slot</b> Dia. <b>12</b> in. Slot/gauze <b>10</b> Length <b>10</b> Set between <b>194</b> ft. and <b>204</b> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 9 Static water level: <b>108</b> ft. below land surface Date <b>4-6-75</b> 10 Pumping level below land surfaces: <b>140</b> ft. after <b>6</b> hrs. pumping <b>380</b> g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield <b>380</b> g.p.m. 11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date 12 Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade 13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite Depth: From <b>0</b> ft. to <b>10</b> ft. 14 Nearest source of possible contamination: ft. <b>44</b> Direction <b>E</b> Type <b>Cesspool</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No 15 Pump: Not installed Manufacturer's name <b>Payer</b> Model number <b>8366</b> HP <b>1/2</b> Volts <b>110</b> Length of drop pipe <b>200</b> ft. capacity <b>400</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other 17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Red Tiger</b> <b>125</b> Business name License No. Address <b>Colby, Ks</b> Signed <b>Leo P. ...</b> Date <b>8-16-76</b> Authorized representative			