

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Thomas</u>		<u>NE 1/4 NE 1/4 SE 1/4</u>	<u>15</u>	<u>T 10 S</u>	<u>R 32 EW</u>
Distance and direction from nearest town, or city street address of well if located within city? <u>462 US Hwy 83 Oakley Ks.</u>					
2 WATER WELL OWNER: <u>Camp Inn Trailer Park</u>					
RR#, St. Address, Box #: <u>462 US Hwy 83</u>				Board of Agriculture, Division of Water Resources	
City, State, ZIP Code: <u>Oakley Ks 67748</u>				Application Number:	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>140</u> ft. ELEVATION: <u>NA</u>			
		Depth(s) Groundwater Encountered 1. <u>59-86</u> ft. 2. <u>109-120</u> ft. 3. _____ ft.			
		WELL'S STATIC WATER LEVEL <u>82</u> ft. below land surface measured on mo/day/yr <u>3-26-97</u>			
		Pump test data: Well water was <u>104</u> ft. after <u>2</u> hours pumping <u>60</u> gpm			
		Est. Yield <u>150+</u> gpm. Well water was <u>110</u> ft. after <u>4</u> hours pumping <u>90</u> gpm			
		Bore Hole Diameter <u>9 7/8</u> in. to <u>140</u> ft. and _____ in. to _____ ft.			
WELL WATER TO BE USED AS:					
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well					
Was a chemical/bacteriological sample submitted to Department? Yes <u>No</u> If yes, mo/day/yr sample was submitted					
Water Well Disinfected? <u>Yes</u> No					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <u>✓</u> Clamped _____ 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ 7 Fiberglass Threaded _____					
Blank casing diameter <u>5</u> in. to <u>130</u> ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.					
Casing height above land surface <u>18</u> in., weight _____ lbs./ft. Wall thickness or gauge No. <u>SDR 26</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) _____ 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From <u>130</u> ft. to <u>90</u> ft. From <u>70</u> ft. to <u>60</u> ft.					
From _____ ft. to _____ ft. From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From <u>130</u> ft. to <u>88</u> ft. From <u>86</u> ft. to <u>30</u> ft.					
From _____ ft. to _____ ft. From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other _____					
Grout Intervals: From <u>88</u> ft. to <u>86</u> ft. From <u>30</u> ft. to <u>0</u> ft. From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) _____ 13 Insecticide storage					
Direction from well? _____ How many feet? <u>60'</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	8	top loess			
8	23	Clay ft. brn., silty sat.	L.Circ @	23	
23	36	Clay tan, totally sat.	L.Circ @	31	
36	52	Clay tan, yellow & totally sat.			
52	59	Clay green-gray non-sat			
59	86	Sd. coarse to gravel, some med. gr.			
86	89	Clay, calcareous, text, non-sat			
89	109	Int. wt, soft f'ly, streaks brn. clay			
109	120	Sd. v. coarse to med.			
120	135	Sd. med to coarse w/ yellow clay streaks			
135	138	yellow clay			
138	140	gray-blue shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>3-26-97</u> and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. <u>608</u> This Water Well Record was completed on (mo/day/yr) <u>3-28-96</u>					
under the business name of <u>Yellow Jacket Drilling</u> by (signature) <u>E. J. Woodell</u>					