


1 LOCATION OF WATER WELL: Fraction **NW 1/4 NW 1/4 NW 1/4** Section Number **32** Township Number **T 11 S** Range Number **R 26 E W**  
 County: **Gove**

Distance and direction from nearest town or city street address of well if located within city?  
**Junction of Castle Rock Road & Kansas Hwy 212, Quinter, Kansas**

2 WATER WELL OWNER: **Grahams 66**  
 RR#, St. Address, Box # : **Interstate 70 & Castle Rock Road** Board of Agriculture, Division of Water Resources  
 City, State, ZIP Code : **Quinter, KS 67752** Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: **4** DEPTH OF COMPLETED WELL **89.8** ft. ELEVATION: **2659**  
 Depth(s) Groundwater Encountered 1 **75.12** ft. 2 ..... ft. 3 ..... ft.  
 WELL'S STATIC WATER LEVEL **75.12** ft. below land surface measured on mo/day/yr **06-13-2006**  
 Pump test data: Well water was ..... ft. after ..... hours pumping ..... gpm  
 Est. Yield **5** gpm: Well water was ..... ft. after ..... hours pumping ..... gpm  
 WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well  
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)  
 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) **10** Monitoring well **OZ-8**  
 Was a chemical/bacteriological sample submitted to Department? Yes ..... No **X** ..... ; If yes, mo/day/yrs sample was submitted  
 Water Well Disinfected? Yes ..... No **X** .....



5 TYPE OF BLANK CASING USED: 1 Steel 2 **PVC** 3 RMP (SH) 4 ABS 5 Wrought iron 6 Asbestos-Cement 7 Fiberglass 8 Concrete tile 9 Other (specify below) CASING JOINTS: Glued ..... Clamped ..... Welded ..... Threaded .....

Blank casing diameter **2** in. to **89.8** ft., Dia ..... in. to ..... ft., Dia ..... in. to ..... ft.  
 Casing height above land surface **-0.2 below** in., weight **0.70** lbs./ft. Wall thickness or gauge No. **sch 40**

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 2 Brass 3 Stainless Steel 4 Galvanized Steel 5 Fiberglass 6 Concrete tile 7 **PVC** 8 RMP (SR) 9 ABS 10 Asbestos-Cement 11 Other (Specify) ..... 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 2 Louvered shutter 3 **Mill slot** 4 Key punched 5 Guazed wrapped 6 Wire wrapped 7 Torch cut 8 Saw cut 9 Drilled holes 10 Other (specify) ..... ft. 11 None (open hole)

SCREEN-PERFORATED INTERVALS: From **87.8** ft. to **89.8** ft., From ..... ft. to ..... ft.  
 GRAVEL PACK INTERVALS: From **85.3** ft. to **89.8** ft., From ..... ft. to ..... ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 **Bentonite** 4 Other .....  
 Grout Intervals: From **85.3** ft. to **1** ft., From **1** ft. to **0 concrete** ft., From ..... ft. to ..... ft.  
 What is the nearest source of possible contamination: 1 Septic tank 2 Sewer lines 3 Watertight sewer lines 4 Lateral lines 5 Cess pool 6 Seepage pit 7 Pit privy 8 Sewage lagoon 9 Feedyard 10 Livestock pens 11 **Fuel storage** 12 Fertilizer storage 13 Insecticide storage 14 Abandoned water well 15 Oil well/Gas well 16 Other (specify below) .....

Direction from well? **East** How many feet? **150**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	topsoil and fill			
1	17	Silt			
17	25	Clayey Silt			
25	35	Sand			
35	60	Sandstone			
60	67	Sand			
67	80	Sandstone			
80	89.8	Sand			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was **1** constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **06-13-06** and this record is true to the best of my knowledge and belief, Kansas Water Well Contractor's Licence No **554** This Water Well Record was completed on (mo/day/yr) **07-18-06** under the business name of **Woofter Pump & Well, Inc.** by (signature) *[Signature]*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send two copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.