

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well:		County <i>Ottawa</i>	Fraction <i>SW 1/4 NW 1/4</i>	Section number <i>21</i>	Township number <i>T 11 S R 3 E</i>	Range number <i>3</i>
2. Distance and direction from nearest town or city: <i>1-S 1-E 1/2 N of Lindsay, Ks.</i>			3. Owner of well: <i>John Kwaddell</i>			
Street address of well location if in city:			R.R. or street: <i>Rt 2</i>			
			City, state, zip code: <i>Minneapolis Ks. 67467</i>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <i>20</i> in. Completion date Well depth <i>110</i> ft. <i>7-26-78</i>		
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
5. Type and color of material		From	To	9. Casing: Material <i>transite</i> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <i>18</i> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia <i>16</i> in. to <i>110</i> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gage No. <i>9</i>		
<i>Top soil</i>		<i>0</i>	<i>3</i>	10. Screen: Manufacturer's name <i>Johnson</i>		
<i>Brown clay</i>		<i>3</i>	<i>24</i>	Type <i>transite</i> Dia. <i>16" MHC</i>		
<i>Sandy clay</i>		<i>24</i>	<i>27</i>	Slot/gauge <i>.0168</i> Length <i>42</i>		
<i>Good sand & gravel</i>		<i>27</i>	<i>40</i>	Set between <i>110</i> ft. and <i>45</i> ft.		
<i>Shale</i>		<i>40</i>	<i>40 1/2</i>	Gravel pack? <input checked="" type="checkbox"/> Size range of material <i>1/2 3/4 1/2"</i>		
<i>Good clean sand rock</i>		<i>40 1/2</i>	<i>110</i>	11. Static water level: <input type="checkbox"/> mo./day/yr. <i>26</i> ft. below land surface Date <i>5-10-77</i>		
<i>Pyrite</i>		<i>110</i>		12. Pumping level below land surfaces: <i>39</i> ft. after <i>2</i> hrs. pumping <i>400</i> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <i>650</i> g.p.m.		
				13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <i>5-10-77</i>		
				14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade		
				15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <i>0</i> ft. to <i>10</i> ft.		
				16. Nearest source of possible contamination: ft. <i>34m</i> Direction <i>East</i> Type <i>ingwell</i> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <i>W.R.R.</i> Model number <i>3-10610</i> HP <i>40</i> Volts Length of drop pipe <i>70</i> ft. capacity <i>650</i> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				(Use a second sheet if needed)		
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Rosenkrantz-Demis 134</i> Business name License No. Address <i>West Bend, Ks 67530</i> Signed <i>Sandy J. Lopez</i> Date <i>10-8-78</i> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

T 11 S R 3 E Sec 21 SW NW NW