


USE TYPEWRITER OR BALL POINT PEN - PRESS FIRMLY, PRINT CLEARLY.

1233W 2SWEFW
T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Logan	Township name Oakley	Fraction SWSE SW 1/4	Section number #2	Town number T 12 S	Range number R 33 W		
Distance and direction from nearest town or city: 5 miles South & 2 1/4 miles East of Monument, Kansas Street address of well location if in city:				3 Owner of well: Kenneth Uhrick Monument, Kansas Address:				
Locate with "X" in section below: N  W E S 1 Mile				Sketch map:				
2 Type and color of material				From	To			
				Top Soil		0	15	
				Clay & sand streaks		15	75	
				Medium to coarse sand & gravel		75	92	
				Clay		92	96	
				Medium to coarse sand & gravel		96	110	
				Ochre		110	113	
				350 ft. 110'				
4 Well depth: 113 ft. Date of completion 7-30-75 Well diameter 28 in.				5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary				
6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well				7 Casing: Material steel Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. Diam. _____ Weight 7-gauge /ft. _____ 0 in. to 83 ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No _____ in. to _____ ft. depth!				
8 Screen: Manufacturer W. A. Brown Type bridge Dia. 16" Slot/gauze 1/8 Length 2" Set between 83 ft. and 103 ft. Fittings: 10' of Cook = 113' Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material 1/4" x 5/8"				9 Static water level: 81 ft. below land surface Date 8-1-75				
10 Pumping level below land surfaces: 105 ft. after 2 hrs. pumping 275 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 275 g.p.m.				11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____				
12 Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> 12 Inches above grade				13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input checked="" type="checkbox"/> & clay Depth: From 0 ft. to 10 ft.				
14 Nearest source of possible contamination: ft. 2,000 Direction East Type Home Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No				15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
16 Remarks: elevation Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley 3102 (TOP) 3102 81 3021				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Western Well & Pump, Inc. 245 Business name _____ License No. _____ Address P.O. Box 852, Colby, Ks. Signed Roy E. Denney Date ext 9/25 Authorized representative				

12 33W 2 SWSE SW

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5