

1 LOCATION OF WATER WELL: County: Ellis Fraction SW 1/4 SW 1/4 SW 1/4 Section Number 27 Township Number T 13 S Range Number R 18 E/W

Distance and direction from nearest town or city street address of well if located within city? 2610 Vine, Hays, KS

2 WATER WELL OWNER: Warren Foskett RR#, St. Address, Box #: 9425 Huhn Blvd. City, State, ZIP Code: Kansas City, Missouri 64133 Board of Agriculture, Division of Water Resources Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: [Diagram showing a 36-section grid with 'X' in the SW section] 4 DEPTH OF COMPLETED WELL: 60 ft. ELEVATION: 2037.13. WELL'S STATIC WATER LEVEL: 39.13 ft. below land surface measured on 10/11/95. Pump test data: Well water was NA ft. after NA hours pumping. Est. Yield: NA gpm. Bore Hole Diameter: 8 in. to 60 ft. WELL WATER TO BE USED AS: 10 Monitoring well. Was a chemical/bacteriological sample submitted? No. Water Well Disinfected? No.

5 TYPE OF BLANK CASING USED: 2 PVC. Blank casing diameter: 2 in. to 40 ft. Dia. Casing height above land surface: -4.32 in. weight. TYPE OF SCREEN OR PERFORATION MATERIAL: 7 PVC. SCREEN OR PERFORATION OPENINGS ARE: 3 Mill slot. SCREEN-PERFORATED INTERVALS: From 40 ft. to 60 ft. GRAVEL PACK INTERVALS: From 38 ft. to 60 ft.

6 GROUT MATERIAL: 2 Cement grout, 3 Bentonite. Grout Intervals: From 0 ft. to 35 ft., From 35 ft. to 38 ft. What is the nearest source of possible contamination: 16 Other (specify below) UST Basin. Direction from well? SW. How many feet? 200.

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows: 0-0.5 Concrete, 0.5-2 Clay, Dark Brown, 2-9 Clay, Brown, 9-33 Clay, Light Brown to Red Brown, 33-48 Clay, Red Brown. Includes MW5, Tag # 113807, Flush; Project Name: ASB Oil Inc.; GeoCore # 61, KDHE # U6 026 676.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10/4/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527. This Water Well Record was completed on (mo/day/yr) 10/14/95 under the business name of GeoCore Services, Inc. by (signature) Dan Roll.