


1 LOCATION OF WATER WELL: County: **ELLIS** Fraction: **NW 1/4 NW 1/4 SE 1/4** Section Number: **5** Township Number: **T 13 S** Range Number: **R 20 E (W)**

Distance and direction from nearest town or city street address of well if located within city?  
**311 2nd St TERR ELLIS, KS**

2 WATER WELL OWNER: **Garry Staab**  
 RR#, St. Address, Box #: **311 2nd St TERR** Board of Agriculture, Division of Water Resources  
 City, State, ZIP Code: **ELLIS KS 67639** Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  
  
 4 DEPTH OF COMPLETED WELL: **64** ft. ELEVATION:  
 Depth(s) Groundwater Encountered 1. **54** ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL: **41** ft. below land surface measured on mo/day/yr **4/17/84**  
 Pump test data: Well water was **18** ft. after **1** hours pumping gpm  
 Est. Yield **25** gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter **10** in. to ft., and in. to ft.  
 WELL WATER TO BE USED AS:  
 5 Public water supply 8 Air conditioning 11 Injection well  
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)  
 Irrigation 4 Industrial **7** Lawn and garden only 10 Observation well  
 Was a chemical/bacteriological sample submitted to Department? Yes No  If yes, mo/day/yr sample was submitted  
 Water Well Disinfected? **Yes** No

5 TYPE OF BLANK CASING USED:  
 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: **Glued** Clamped  
**2 PVC** 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded  
 7 Fiberglass Threaded  
 Blank casing diameter **5** in. to ft., Dia in. to ft., Dia in. to ft.  
 Casing height above land surface: **21** in., weight lbs./ft. Wall thickness or gauge No. **SPR-26**  
 TYPE OF SCREEN OR PERFORATION MATERIAL:  
 1 Steel 3 Stainless steel 5 Fiberglass **7 PVC** 10 Asbestos-cement  
 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)  
 9 ABS 12 None used (open hole)  
 SCREEN OR PERFORATION OPENINGS ARE:  
 1 Continuous slot 3 Mill slot 5 Gauzed wrapped **8 Saw cut** 11 None (open hole)  
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes  
 7 Torch cut 10 Other (specify)  
 SCREEN-PERFORATED INTERVALS: From **44** ft. to **64** ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From **30** ft. to **64** ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: **1** Neat cement **2** Cement grout 3 Bentonite 4 Other  
 Grout Intervals: From **5** ft. to **15** ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination:  
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well  
**2** Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well  
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)  
 13 Insecticide storage  
 Direction from well? **West** How many feet? **50**

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	10	TOP SOI			
10	35	FINE GREY SAND			
35	54	BROWN CLAY			
54	63	COARSE TO MED GREY 3 RSD SAND MIXED WITH WHITE GRAVEL			
63	64	SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was **1** constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **4/21/84** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **276** This Water Well Record was completed on (mo/day/yr) **4/21/84** under the business name of **LUSA Water Well** by (signature) **John Lee**

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.