



Pestinger Drilling Company

1711 North Fifth Street / Salina, Kansas 67401 / Telephone 913 825-1932

1 Location of well:	County SALINE	Township name	Fraction NE$\frac{1}{4}$ NE$\frac{1}{4}$ NE$\frac{1}{4}$	Section number 13	Town number 13 S	Range number 3 W
Distance and direction from nearest town or city: 3 MILES NORTH SALINA, KS. <small>Street address of well location if in city:</small>			3 Owner of well: GEORGE L. FRISBIE TRUST #2 Address: BOX 278 GYPSUM, KS.			
Locate with "X" in section below: <div style="text-align: center;">N W ——— E S 1 Mile</div>		Sketch map: OHIO ST		4 Well depth: <u>105</u> ft. Date of completion _____ Well diameter <u>8</u> in. <u>4-9-80</u>		
2 Type and color of material		From		To		5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
						6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input checked="" type="checkbox"/> Test well <input type="checkbox"/>
TOPSOIL		6		6		7 Casing: Material <u>PVC</u> Height: above 250 <u>24</u> in. Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>24</u> in. Diam. <u>5</u> in. Weight <u>200</u> lbs./ft. <u>0</u> in. to <u>105</u> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No _____ in. to _____ ft. depth
SILT, SANDY GREY & TAN		6		9		8 Screen: Manufacturer <u>JESS & LOWELL</u> Type <u>SLOT</u> Dia. <u>1 1/8" 5"</u> Slot/gauze <u>1/8"</u> Length <u>30"</u> Set between <u>75</u> ft. and <u>105</u> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>4</u>
SANDSTONE, YELLOW V FINE		9		11		9 Static water level: <u>53</u> ft. below land surface Date <u>4-9-80</u>
SHALE, L GREY INBEDDED W/SANDSTONE		11		16		10 Pumping level below land surfaces: <u>54</u> ft. after <u>2</u> hrs. pumping <u>30</u> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <u>50</u> g.p.m.
SANDSTONE, WHITE, SOME CLAY MIXED W/ BROWN SOFT ZONES		16		79		11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____
SHALE GREY		79		81		12 Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade
SANDSTONE FINE TO MED. L BROWN		81		100		13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> _____ Depth: From <u>0</u> ft. to <u>11</u> ft.
SHALE GREY MIXED W/QUARTZITE		100		?		14 Nearest source of possible contamination: ft. <u>1000</u> Direction <u>E</u> Type <u>BARNYARD</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
(use a second sheet if needed)						15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
						16 Remarks: elevation
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PESTINGER DRILLING CO. Business name _____ License No. _____ Address <u>SALINA, KS.</u> Signed <u>Paul C. Pestinger</u> Authorized representative <u>4-14-80</u>

13
300 / 3 AVE NENE