

[1] LOCATION OF WATER WELL:		Fraction	Township Number	Range Number
County: Saline	SE ¼ NE ¼ SE ¼	Section Number 26	T 14 S	R 3 E W
Distance and direction from nearest town or city street address of well if located within city? 2222 S. Ninth Street, Salina				
[2] WATER WELL OWNER: Warta Buick				
RR#, St. Address, Box # : 2222 S. 9th	Board of Agriculture, Division of Water Resources			
City, State, ZIP Code : Salina, Kansas 67401	Application Number:			
[3] LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	[4] DEPTH OF COMPLETED WELL 30 . . . ft. ELEVATION:			
N ↑ ↓ S W ← → → → → E	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
	WELL'S STATIC WATER LEVEL . . . 21.5 . . . ft. below land surface measured on mo/day/yr . . . 2/13/2008			
	Pump test data: Well water was . . . NA . . . ft. after . . . hours pumping . . . gpm			
	Est. Yield . . . NA . . . gpm: Well water was . . . ft. after . . . hours pumping . . . gpm			
	Bore Hole Diameter . . . 8 . . . in. to . . . 30 . . . ft., and . . . in. to . . . ft.			
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued . . . Clamped . . .		
1 Steel 3 RMP (SR)		Welded		
(2) PVC 4 ABS		Threaded. ✓		
Blank casing diameter . . . 2 . . . in. to . . . 15 . . . ft. Dia . . . in. to . . . ft. Dia . . . in. to . . . ft.		Wall thickness or gauge No. . . Sch. 40		
Casing height above land surface . . . in., weight . . . lbs./ft.				
TYPE OF SCREEN OR PERFORATION MATERIAL		(7) PVC 10 Asbestos-cement		
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		11 Other (specify)		
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)				
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)		
1 Continuous slot (3) Mill slot 6 Wire wrapped 9 Drilled holes				
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)				
SCREEN-PERFORATED INTERVALS: From . . . 15 . . . ft. to . . . 30 . . . ft.		From . . . ft. to . . . ft.		
GRAVEL PACK INTERVALS: From . . . 13 . . . ft. to . . . 30 . . . ft.		From . . . ft. to . . . ft.		
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS				
0	1	Asphalt,		
1	6	Clay, sl. silty, plastic, moist, no odor, Med. Bro		
6	13	Silt, sand, dry, no odor, Brown		
13	19	Silt, sl. clayey, dry, no odor, Brown-Gray		
19	26	Clay, silty, plastic, dry, no odor, Red-Brown		
26	30	Silt, clayey to sandy, saturated, no odor, Tan		
		MW11 , Tag # 0042461 , Flushmount		
		Project Name: Warta Buick - Monitoring		
		GeoCore # 57 , KDHE # U5 085 00622		
[7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) . . . 2/13/2008 . . . and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. . . . 527 . . . This Water Well Record was completed on (mo/day/yr) . . . 2/18/2008 . . . under the business name of GeoCore, Inc. by (signature) <i>Dan Bell</i>				

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.