

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Saline		Fraction NE ¼ SE ¼ NE ¼ SE ¼		Section Number 11	Township No. T 14 S	Range Number R 3 ☐ E ☒ W				
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 417 Bishop Street Salina, Kansas				Global Positioning System (GPS) information: Latitude: 38.846949 (in decimal degrees) Longitude: -97.613507 (in decimal degrees) Elevation: 1225.74 ft Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: Thales/MobileMapp) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☒ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m						
2 WATER WELL OWNER: KDHE/BER SWP-1 RR#, Street Address, Box #: 1000 SW Jackson Suite 410 City, State, ZIP Code : Topeka, KS. 66612										
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="margin: auto;"> <tr> <td style="width: 20px;">NW</td> <td style="width: 20px;">NE</td> </tr> <tr> <td style="width: 20px;">SW</td> <td style="width: 20px;">SE</td> </tr> </table> S ----- 1 mile -----		NW	NE	SW	SE	4 DEPTH OF COMPLETED WELL 39.48 ft. Depth(s) Groundwater Encountered (1) 26.18 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 26.15 ft. below land surface measured on mo/day/yr. 6/17/09 Pump test data: Well water was ft. after hours pumping gpm EST. YIELD gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 8 in. to 40 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☒ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☒ Yes ☐ No If yes, mo/day/yr sample was submitted 6/17/09 Water well disinfected? ☐ Yes ☒ No				
NW	NE									
SW	SE									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded Casing diameter 2 in. to 30 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 0 in., Weight 0.69 lbs./ft., Wall thickness or gauge No. 0.154 in. TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 30 ft. to 40 ft., From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 27 ft. to 40 ft., From ft. to ft., From ft. to ft.										
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 0.5 ft. to 27 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well 1-1DCE Plume Direction from well NW Distance from well 0 ft.										
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS					
0	8	Silty Clay								
8	13	Silt								
13	17	Silty Clay								
17	22	Silt								
22	26	Sand								
26	36	Clayey Silt								
36	40	Sand								
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 6/15/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. Exempt This Water Well Record was completed on (mo/day/year) 7/22/09 under the business name of KDHE/BER by (signature) <i>for</i> <i>Verano</i>										
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .										