

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Saline		NE ¼ NE ¼ NE ¼		2		T 14 S		R 3 EW	
Distance and direction from nearest town or city street address of well if located within city? 1745 N. 9th Street, Salina, Kansas									
2 WATER WELL OWNER: SEI Partners RR#, St. Address, Box #: 129 S. 8th City, State, ZIP Code: Salina, Ks. 67401 Board of Agriculture, Division of Water Resources Application Number:									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: .45 ft. ELEVATION: Depth(s) Groundwater Encountered 1. 27 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL: 24.72 ft. below land surface measured on mo/day/yr 04-04-93 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter: 10 in. to 45 ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Pump Test Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒							
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 4 in. to 25 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface in., weight lbs./ft. Wall thickness or gauge No. TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes SCREEN-PERFORATED INTERVALS: From 25 ft. to 45 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 23 ft. to 45 ft., From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 21 ft., From 21 ft. to 23 ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) Direction from well? southwest How many feet? 25									
LITHOLOGIC LOG			PLUGGING INTERVALS						
FROM	TO		FROM	TO					
0	1.5	DK BRN ORG CLY			PW				
1.5	5	DK MED BRN SLTY CLY			Flush mount cover				
5	7	DK BRN SLTY CLY, FRM							
7	15	MED RED BRN SLTY CLY							
15	20	DK MED BRN SLTY CLY							
20	27	DK MED GY BRN SLTY CLY							
27	30	MED BRN TO GY BRN SLTY TO SDY CLY							
30	34	VF TO F SND, MED BRN							
34	45	VF TO M SND, MED BRN							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 03-23-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 04-30-93 under the business name of GeoCore Services, Inc. by (signature) Dan Reel									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.									