

1 LOCATION OF WATER WELL: County: <u>Saline</u>	Fraction <u>SW</u> $\frac{1}{4}$ <u>SW</u> $\frac{1}{4}$ <u>NE</u> $\frac{1}{4}$	Section Number <u>25</u>	Township Number T <u>14</u> <u>S</u>	Range Number R <u>3</u> <u>E</u>
--	---	-----------------------------	---	-------------------------------------

Distance and direction from nearest town or city street address of well if located within city?

2087 Wesley

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP Code : <u>Saline Kansas 67401</u>	Board of Agriculture, Division of Water Resources Application Number: <u>1235</u>
--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: <u>55</u> ft. ELEVATION: <u>1235</u>
--	---

Depth(s) Groundwater Encountered 1 23 ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 23 ft. below land surface measured on mo/day/yr 7-11-92

Pump test data: Well water was 27 ft. after 1 hours pumping 15 gpm

Est. Yield 30 gpm Well water was ft. after hours pumping gpm

Bore Hole Diameter 8 1/2 in. to 37 ft., and 5 1/2 in. to 55 ft.

WELL WATER TO BE USED AS:

1 Domestic	3 Feedlot	6 Oil field water supply	9 Dewatering	12 Other (Specify below)
2 Irrigation	4 Industrial	<u>7</u> Lawn and garden only	10 Monitoring well	

Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes X No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped
------------------------------	----------------	-----------------	---

1 Steel

2 PVC

Blank casing diameter 5 in. to 45 ft. Dia in. to ft. Dia in. to ft.

Casing height above land surface 18 in. weight 160 lbs./ft. Wall thickness or gauge No. SPR26

3 RMP (SR)

4 ABS

7 Fiberglass

6 Asbestos-Cement

9 Other (specify below)

Welded

Threaded

TYPE OF SCREEN OR PERFORATION MATERIAL:	10 Asbestos-cement
---	--------------------

1 Steel

2 Brass

3 Stainless steel

4 Galvanized steel

5 Fiberglass

6 Concrete tile

7 PVC

8 RMP (SR)

9 ABS

11 Other (specify)

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
-------------------------------------	------------------	-----------	---------------------

1 Continuous slot

2 Louvered shutter

3 Mill slot

4 Key punched

6 Wire wrapped

7 Torch cut

9 Drilled holes

10 Other (specify)

SCREEN-PERFORATED INTERVALS:	From <u>45</u> ft. to <u>55</u> ft.	From ft. to ft.	From ft. to ft.
------------------------------	-------------------------------------	-------------------------------------	-------------------------------------

GRAVEL PACK INTERVALS:	From <u>22</u> ft. to <u>55</u> ft.	From ft. to ft.	From ft. to ft.
------------------------	-------------------------------------	-------------------------------------	-------------------------------------

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
-------------------	---------------	----------------	-------------	-------------------

Grout Intervals: From 0 ft. to 22 ft. From ft. to ft. From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
<u>3</u> Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	

Direction from well? South How many feet? 27

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	Compacted Dirt			
5	12	Clay			
5	22	Silt + Fine Sand			
22	37	Fine Sand + Clay Mixed			
37	40	Fine Sand			
40	41	Clay (Dark)			
41	55	Sand + Gravel (Median + Coarse)			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>1</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>7-18-92</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. This Water Well Record was completed on (mo/day/yr) <u>7-18-92</u> under the business name of <u>Owner</u> by (signature) <u>Jack Milleson</u>
--