

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Saline	SE 1/4 NE 1/4 SE 1/4	26	T 14 S	R 3 EW

Distance and direction from nearest town or city street address of well if located within city?

2222 South Ninth, Salina, Kansas

2	WATER WELL OWNER:	Warta Buick	
	RR#, St. Address, Box # :	2222 S. Ninth	Board of Agriculture, Division of Water Resources
	City, State, ZIP Code :	Salina, Ks. 67401	Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: 28 ft. ELEVATION: ft.

Depth(s) Groundwater Encountered 1. 22 ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 16.8 ft. below land surface measured on mo/day/yr 06-14-93

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter: 7 5/8 in. to 28 ft., and in. to ft.

WELL WATER TO BE USED AS:

5 Public water supply	8 Air conditioning	11 Injection well
1 Domestic	3 Feedlot	6 Oil field water supply
2 Irrigation	4 Industrial	7 Lawn and garden only
		9 Dewatering
		12 Other (Specify below)

10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes. No. X.; If yes, mo/day/yr sample was submitted

Water Well Disinfected? Yes No X

5 TYPE OF BLANK CASING USED:		5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded
② PVC	4 ABS	7 Fiberglass		Threaded X
Blank casing diameter 2 in. to 13 ft., Dia in. to ft., Dia in. to ft.				
Casing casing above land surface 30 in., weight lbs./ft. Wall thickness or gauge No. Sch. . 40				
TYPE OF SCREEN OR PERFORATION MATERIAL:				
1 Steel	3 Stainless steel	5 Fiberglass	⑦ PVC	10 Asbestos-cement
2 Brass	4 Galvanized steel	6 Concrete tile	8 RMP (SR)	11 Other (specify)
			9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:				
1 Continuous slot	③ Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes	
		7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 13 ft. to 28 ft., From ft. to ft., From ft. to ft.				
GRAVEL PACK INTERVALS: From 11 ft. to 28 ft., From ft. to ft., From ft. to ft.				

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other
Grout Intervals: From 0 ft. to 9 ft., From 9 ft. to 11 ft., From ft. to ft.
What is the nearest source of possible contamination:
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)
13 Insecticide storage
Direction from well? south southeast How many feet? 350

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3.5	CLY, DK GY/BRN, SILTY			
3.5	7.5	SILTY, GY/BRN, CLAYEY			
7.5	9.5	CLAY, GY/BRN, SILTY			
9.5	14.5	CLAY, DK GY/BRN			
14.5	16.5	SILTY, GY/BRN, CLAYEY			
16.5	18.5	CLAY, GY/BRN, SILTY			
18.5	21.5	CLAY, LT RD/BRN, SILTY			
21.5	24.5	CLAY, DK RD/BRN, SILTY			
24.5	28	CLAY, DK RD/BRN, SNDY			
					MW8
					Above ground cover
					KDHE site id 00080600

7. CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 05-21-93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 07-01-93 under the business name of GeoCore Services, Inc. by (signature) Dale Rehl