


1 LOCATION OF WATER WELL		Fraction	Section Number		Township Number		Range Number	
County: Saline		NW 1/4 NW 1/4 NW 1/4	36		T 14 S		R 3 EW	
Distance and direction from nearest town or city?				Street address of well if located within city?				
				2532 Highland				
2 WATER WELL OWNER: Bill Hobough								
RR#, St. Address, Box # : 2532 Highland				Board of Agriculture, Division of Water Resources				
City, State, ZIP Code : Salina, Ks. 67401				Application Number:				
3 DEPTH OF COMPLETED WELL: 54 ft. Bore Hole Diameter: 8 1/2 in. to 54 ft., and in. to ft.								
Well Water to be used as:								
1 Domestic		3 Feedlot		5 Public water supply		8 Air conditioning		
2 Irrigation		4 Industrial		6 Oil field water supply		9 Dewatering		
		☒ Lawn and garden only		10 Observation well		11 Injection well		
						12 Other (Specify below)		
Well's static water level: 22 ft. below land surface measured on 4 month 28 day 81 year								
Pump Test Data: Well water was 23 ft. after 1 hours pumping 15 gpm								
Est. Yield 80 gpm: Well water was 25 ft. after 1 hours pumping 40 gpm								
4 TYPE OF BLANK CASING USED:								
1 Steel		☒ RMP (SR)		5 Wrought iron		8 Concrete tile		
2 PVC		4 ABS		6 Asbestos-Cement		9 Other (specify below)		
				7 Fiberglass		Casing Joints: Glued ☒ Clamped		
						Welded		
						Threaded		
Blank casing dia 5 in. to 48 ft., Dia in. to ft., Dia in. to ft.								
Casing height above land surface 12 in., weight 200 lbs./ft. Wall thickness or gauge No 214								
TYPE OF SCREEN OR PERFORATION MATERIAL:								
1 Steel		3 Stainless steel		5 Fiberglass		7 PVC		
2 Brass		4 Galvanized steel		6 Concrete tile		9 ABS		
						10 Asbestos-cement		
						11 Other (specify)		
						12 None used (open hole)		
Screen or Perforation Openings Are:								
1 Continuous slot		3 Mill slot		5 Gauzed wrapped		☒ Saw cut		
2 Louvered shutter		4 Key punched		6 Wire wrapped		9 Drilled holes		
				7 Torch cut		10 Other (specify)		
Screen-Perforation Dia 5 in. to 6 ft., Dia in. to ft., Dia in. to ft.								
Screen-Perforated Intervals: From 48 ft. to 54 ft., From ft. to ft., From ft. to ft.								
Gravel Pack Intervals: From ft. to ft., From ft. to ft., From ft. to ft.								
5 GROUT MATERIAL:								
1 Neat cement		☒ Cement grout		3 Bentonite		4 Other		
Grouted intervals: From 1 ft. to 10 ft., From ft. to ft., From ft. to ft.								
What is the nearest source of possible contamination:								
1 Septic tank		4 Cess pool		7 Sewage lagoon		10 Fuel storage		
2 Sewer lines		5 Seepage pit		8 Feed yard		11 Fertilizer storage		
3 Lateral lines		6 Pit privy		9 Livestock pens		12 Insecticide storage		
						14 Abandoned water well		
						15 Oil well/Gas well		
						16 Other (specify below)		
						☒ Watertight sewer lines		
Direction from well North How many feet 40 ? Water Well Disinfected? Yes ☒ No								
Was a chemical/bacteriological sample submitted to Department? Yes ☒ No ☒ If yes, date sample was submitted month day year Pump Installed? Yes ☒ No								
If Yes: Pump Manufacturer's name Red Jacket Model No. n8cc HP 1 Volts 230								
Depth of Pump Intake 40 ft. Pumps Capacity rated at 1.8 gal./min.								
Type of pump: ☒ Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other								
6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on 4 month 28 day 81 year								
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 388								
This Water Well Record was completed on 5 month 5 day 81 year under the business name of Pestinger Pump Service by (signature) <i>Paul Pestinger</i>								
7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	
		1	10	Dirt				
		11	30	Fine Sand				
		30	35	Clay				
		36	50	Small Gravel				
		50	51	Clay				
		51	54	Small Gravel				
ELEVATION:								
Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. 4. ft. (Use a second sheet if needed)								
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.								

OFFICE USE ONLY

T

14

R

W

END

SEC.

36

N 1/4 1/4 1/4 1/4