

1 LOCATION OF WATER WELL:	Fraction <u>SE</u> <u>SW</u> <u>SW</u> <u>NE</u>	Section Number <u>36</u>	Township Number <u>14</u> S	Range Number <u>9</u> E
County: <u>Saline</u>	<u>8 1/4</u> <u>1/4</u> <u>8 1/4</u> <u>1/4</u>			

Distance and direction from nearest town or city street address of well if located within city?

2 WATER WELL OWNER:	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	Application Number:
City, State, ZIP Code:	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: <u>58 1/2</u> ft. ELEVATION: <u>1241</u>
--	---

	Depth(s) Groundwater Encountered 1. <u>27</u> ft. 2. <u>58 1/2</u> ft. 3. <u>1241</u> ft.
	WELL'S STATIC WATER LEVEL <u>27</u> ft. below land surface measured on mo/day/yr <u>5-27-91</u>
	Pump test data: Well water was <u>27 1/2</u> ft. after <u>1</u> hours pumping <u>18</u> gpm
	Est. Yield <u>50</u> gpm; Well water was <u>27 1/2</u> ft. after <u>1</u> hours pumping <u>18</u> gpm
Bore Hole Diameter <u>8 1/2</u> in. to <u>30</u> ft., and <u>5 1/2</u> in. to <u>58 1/2</u> ft.	
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes <u>X</u> No <u>X</u>	If yes, mo/day/yr sample was submitted
Water Well Disinfected? Yes <u>X</u> No <u>X</u>	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	10 Asbestos-cement
Blank casing diameter <u>5</u> in. to <u>48 1/2</u> ft. Dia. <u>160 LB</u> lbs./ft. Wall thickness or gauge No. <u>214</u>			
Casing height above land surface <u>24</u> in. weight <u>160 LB</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	2 Mill slot	3 Gauzed wrapped	4 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
SCREEN-PERFORATED INTERVALS:			
From <u>48 1/2</u> ft. to <u>58 1/2</u> ft.			
GRAVEL PACK INTERVALS:			
From <u>24</u> ft. to <u>58 1/2</u> ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From <u>0</u> ft. to <u>24</u> ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? <u>North + East</u>				
How many feet? <u>15' + 17'</u>				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	8'	Compacted dirt + silt			
8'	30'	Fine SAND + clay mixed - Light Brown			
30'	39'	Fine SAND			
39'	58 1/2'	Medium to coarse SAND + gravel			
58 1/2'		Dark Brown clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>5-30-91</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>523</u> This Water Well Record was completed on (mo/day/yr) <u>5-30-91</u> under the business name of <u>Mad Well Service</u> by (signature) <u>Matthew Soukup</u>
--