

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

47,994

1 LOCATION OF WATER WELL: County: Saline Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 5 miles West & 1 mile North of Salina, KS		Fraction $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ 1		Section Number 1		Township No. T 14 S		Range Number R 4 ☐ E ☒ W																																																																			
2 WATER WELL OWNER: Bruce Wyatt RR#, Street Address, Box #: 4401 W. State St. City, State, ZIP Code : Salina, KS 67401		Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																									
3 LOCATE WELL WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 121 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... 20 ft. below land surface measured on mo/day/yr... 7/16/12 Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD 250-300 gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter 20 in. to 121 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																																																									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 10 in. to 81 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface..... 16 in., Weight 8.878 lbs./ft., Wall thickness or gauge No. 413 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From..... 81 ft. to 121 ft., From ft. to ft. From..... ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From..... 20 ft. to 121 ft., From ft. to ft. From..... ft. to ft., From ft. to ft.																																																																											
6 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☐ Bentonite ☐ Other Grout Intervals: From..... 0 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well Distance from well																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>2</td> <td>Topsoil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2</td> <td>30</td> <td>Clay, red</td> <td></td> <td></td> <td></td> </tr> <tr> <td>30</td> <td>90</td> <td>Clay, tan</td> <td></td> <td></td> <td></td> </tr> <tr> <td>90</td> <td>110</td> <td>Creek gravel w/clay balls (50/50)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>110</td> <td>120</td> <td>Creek gravel, red</td> <td></td> <td></td> <td></td> </tr> <tr> <td>120</td> <td>121</td> <td>Shale, red</td> <td></td> <td></td> <td></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	2	Topsoil				2	30	Clay, red				30	90	Clay, tan				90	110	Creek gravel w/clay balls (50/50)				110	120	Creek gravel, red				120	121	Shale, red																											
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	2	Topsoil																																																																									
2	30	Clay, red																																																																									
30	90	Clay, tan																																																																									
90	110	Creek gravel w/clay balls (50/50)																																																																									
110	120	Creek gravel, red																																																																									
120	121	Shale, red																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 7/16/12 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 138 This Water Well Record was completed on (mo/day/year) 138 under the business name of Peterson Irrigation, Inc. by (signature) <i>Mike Peterson</i>																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. <i>PLEASE PRESS FIRMLY</i> and <i>PRINT</i> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											