

The Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Bonnie E. Hibbert

Wallace Co.

12-5-88

Location: NW 31-14-42

3 miles West 5 miles So. 1 mile West
½ mile No. ½ mile East 452' North of
existing well from Weskam

Static water level 160'

Test #2

0	6	Top soil
6	20	Sandy Clay
20	50	Fine sandy & brown sandy clay
50	95	Tan clay & fine sand & hard streaks
95	110	Fine medium coarse sand
110	170	Fine medium coarse sand, small gravel small hard & small clay 5%
170	178	Fine medium coarse sand, small gravel loose
178	182	Fine medium sand tight
182	220	Fine medium coarse sand & fine gravel loose
220	225	Brown sandy clay
225	230	Fine medium coarse sand fine gravel loose
230	255	Brown sandy clay loose
255	270	Fine medium coarse sand & fine gravel loose
270	275	Clay & white & brown rock very hard
275	290	Fine medium coarse sand, fine gravel loose
290	292	Sandy clay loose
292	297	Fine medium coarse sand, fine gravel loose
297	305	Brown sandy clay hard
305	327	Fine medium coarse sand & fine gravel loose
✓	327	335 sandy clay tight Spots
	335	345 Fine medium sand loose
	345	352 Yellow clay tight
	352	360 shale hard & tight