

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Saline</u>		<u>NW</u> $\frac{1}{4}$ <u>NW</u> $\frac{1}{4}$ <u>SE</u> $\frac{1}{4}$	<u>3</u>	<u>T</u> <u>15</u> <u>S</u>	<u>R</u> <u>3</u> <u>E/W</u>
Distance and direction from nearest town or city street address of well if located within city? <u>1900 feet west of Centennial and 600 feet North of Wall St.</u>					
2 WATER WELL OWNER: <u>Salina Airport Authority</u>					
RR#, St. Address, Box # : <u>3237 Arnold Ave.</u>					
City, State, ZIP Code : <u>Salina, Kansas 67401</u>					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL <u>30</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered <u>1</u> <u>16</u> ft. 2. <u>17.47</u> ft. 3. <u>17.47</u> ft.			
		WELL'S STATIC WATER LEVEL <u>17.47</u> ft. below TOC measured on mo/day/yr <u>08-09-94</u>			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter <u>7 5/8</u> in. to <u>30</u> ft. and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
Was a chemical/bacteriological sample submitted to Department? Yes _____ No <u>X</u> ; If yes, mo/day/yr sample was submitted _____					
Water Well Disinfected? Yes _____ No <u>X</u>					
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued _____ Clamped _____
<u>2</u> PVC		4 ABS	6 Asbestos-Cement	9 Other (specify below)	Welded _____
			7 Fiberglass		Threaded <u>X</u>
Blank casing diameter <u>2</u> in. to <u>15</u> ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.					
Casing height above land surface <u>+30</u> in. weight _____ lbs./ft. Wall thickness or gauge No. <u>sch 40</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel	5 Fiberglass	8 RMP (SR)	10 Asbestos-cement
2 Brass		4 Galvanized steel	6 Concrete tile	9 ABS	11 Other (specify) _____
					12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		<u>3</u> Mill slot	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
2 Louvered shutter		4 Key punched	6 Wire wrapped	9 Drilled holes	
			7 Torch cut	10 Other (specify) _____	
SCREEN-PERFORATED INTERVALS: From <u>15</u> ft. to <u>30</u> ft. From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From <u>13</u> ft. to <u>30</u> ft. From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement <u>2</u> Cement grout <u>3</u> Bentonite 4 Other _____					
Grout Intervals: From <u>0</u> ft. to <u>11</u> ft. From <u>11</u> ft. to <u>13</u> ft. From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
<u>2</u> Sewer lines		5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines		6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? <u>East</u> How many feet? <u>700</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Clay, mod brn, slty, soft, dry			
2	7	Clay, lt gn, stiff, 1 plst, damp			
7	21.5	Clay, mod rd/brn, soft - firm, med plst sl tr grvl, damp - moist			
21.5	27	Clay, v lt brn, mod - v grvly, soft, med plst, sat.			
27	30	Shale, gy, reworked with tr calc clst			
MW3 - Above Grade Cover					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>(1)</u> constructed, <u>(2)</u> reconstructed, or <u>(3)</u> plugged under my jurisdiction and was completed on (mo/day/year) <u>08-09-94</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>527</u> This Water Well Record was completed on (mo/day/yr) <u>08-16-94</u> under the business name of <u>GeoCore Services, Inc.</u> by (signature) <u>Doug Ray</u>					