

USE TYPEWRITER OR BALL
POINT PEN. PRESS FIRMLY.
PRINT CLEARLY.

WATER WELL RECORD KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County: <u>Saline</u>		Fraction: <u>SE</u> <u>SE</u> <u>SE</u> <u>SW 1/4</u> <u>SW 1/4</u> <u>SW 1/4</u>		Section number <u>24</u>	Township number T <u>15</u> S	Range number R <u>4</u> E
2. Distance and direction from nearest town or city: <u>15 - 2W - 1/8 N</u> Street address of well location if in city: <u>Smolan, Kans.</u>				3. Owner of well: <u>Richard Kelley</u> R.R. or street: <u>R.R. 1</u> City, state, zip code: <u>Smolan, Mo. 67479</u>		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile		Sketch map: <u>E</u> 		6. Bore hole dia. <u>8</u> in. Completion date <u>1-22-77</u> Well depth <u>56</u> ft. <u>1-22-77</u>		
5. Type and color of material		From	To	7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
<u>Chop Shale</u>		<u>0</u>	<u>2</u>	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<u>Dark Clay</u>		<u>2</u>	<u>9</u>	9. Casing: Material <u>PVC</u> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>24</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u> </u> lbs./ft. Dia. <u>4</u> in. to <u>38</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>14</u>		
<u>Buff Silty Clay</u>		<u>9</u>	<u>19</u>	10. Screen: Manufacturer's name <u>Certain Seal</u> Type <u>Pvc</u> Dia. <u>4</u> in. Slot/gauze <u>1/32</u> Length <u>20</u> Set between <u>56</u> ft. and <u>46</u> ft. <u>39</u> ft. and <u>29</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>1/4 - 1/8</u>		
<u>V.V. Fine sands & sand Rock gravel</u>		<u>19</u>	<u>19 1/2</u>	11. Static water level: <u> </u> mo./day/yr. <u>21</u> ft. below land surface Date <u>1-22-77</u>		
<u>Buff Clay</u>		<u>19 1/2</u>	<u>36</u>	12. Pumping level below land surfaces: <u>24</u> ft. after <u>1 1/2</u> hrs. pumping <u>7</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>7-12</u> g.p.m.		
<u>V.V. Fine sands - Rock gravel</u>		<u>36</u>	<u>40 1/2</u>	13. Water sample submitted: <u> </u> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u> </u>		
<u>Buff Reddish Clay</u>		<u>40 1/2</u>	<u>52</u>	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>24</u> inches above grade		
<u>V.V. Fine sands & Rock gravel</u>		<u>52</u>	<u>57</u>	15. Well grouted? <u>Yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>5</u> ft. to <u>15</u> ft.		
<u>Blue & Red shale</u>		<u>57</u>	<u>60</u>	16. Nearest source of possible contamination: ft. <u>70</u> Direction <u>N</u> Type <u>Septic</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Deussen, Inc.</u> <u>138A</u> Business name <u> </u> License No. <u> </u> Address <u> </u> Signed <u>William Deussen</u> Date <u>2-1-77</u> Authorized representative		
18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks: <u>Mr. Kelley will install his own pump.</u> <u>and pour his 4 ft. of concrete slab</u> <u>around well. He knows this is in</u> <u>Regulation.</u>				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5