

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>SALINE</u>		Fraction <u>NW 1/4 SE 1/4 SE 1/4</u>		Section number <u>30</u>	Township number <u>T 16 S R 3</u>		Range number <u>3</u>				
2. Distance and direction from nearest town or city: <u>3 1/4 mi. N of LINCOLN, KS.</u>				3. Owner of well: <u>Karl Esping</u> R.R. or street: <u>109 N. CHERRY</u> City, state, zip code: <u>LINCOLN, KS. 67456</u>							
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W <table border="1" style="display: inline-table;"><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile</div> <u>STOCK WELL</u>				NW	NE	SW	SE	6. Bore hole dia. <u>8</u> in. Completion date <u>4-31-79</u> Well depth <u>81</u> ft.			
NW	NE										
SW	SE										
5. Type and color of material				7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary							
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other							
				9. Casing: Material <input type="checkbox"/> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>24</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u>2</u> lbs./ft. Dia. <u>4</u> in. to <u>51</u> ft. depth Wall Thickness: inches or Dia. <u>4</u> in. to <u>51</u> ft. depth gage No. <u>25</u>							
				10. Screen: Manufacturer's name <u>PERIPLASTICS</u> Type <u>PVC</u> Dia. <u>4"</u> Slot/gauze <u>1/32</u> Length <u>30</u> Set between <u>51</u> ft. and <u>81</u> ft. Gravel pack? <u>YES</u> Size range of material <u>14 in</u>							
				11. Static water level: <u>30</u> ft. below land surface Date <u>4-31-79</u> 12. Pumping level below land surfaces: <u>65</u> ft. after <u>2</u> hrs. pumping <u>3</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>3</u> g.p.m.							
13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>				14. Well head completion: <u>24</u> inches above grade <input type="checkbox"/> Pitless adapter							
15. Well grouted? <u>YES</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.				16. Nearest source of possible contamination: <u>OIL WELL</u> ft. <u>1000</u> Direction <u>S</u> Type <u>WELL</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No							
17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>PETERSON IRRIGATION 138</u> Business name License No. <u> </u> Address <u>Box 150 LINCOLN, KS.</u> Signed <u>Mike Peterson</u> Date <u>5-2-79</u> Authorized representative							
18. Elevation:		19. Remarks:		20. Water well contractor's certification:							
Topography: <input checked="" type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley											

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5