

Sent 11/1/77

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.WATER WELL RECORD
KSA 82a-1201-1215Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | | |
|---|--|-------------------------|---|---|----------------------------------|------------------------------|
| 1. Location of well: | | County <u>SALINE</u> | Fraction <u>SE 1/4 SW 1/4 SE 1/4</u> | Section number <u>33</u> | Township number T <u>16</u> S | Range number R <u>3</u> W |
| 2. Distance and direction from nearest town or city: <u>3 N</u> Street address of well location if in city: <u>LINDSBORG, KS</u> | | | | 3. Owner of well: <u>GORDON BENGSTON</u> R.R. or street: <u>R.R. #1</u> City, state, zip code: <u>LINDSBORG KS 67456</u> | | |
| 4. Locate with "X" in section below: | | Sketch map: | | 6. Bore hole dia. <u>30</u> in. Completion date <u>10-12-77</u> Well depth <u>59</u> ft. | | |
| | | | | 7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary | | |
| 5. Type and color of material | | From | To | 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | | |
| Top Soil | | 0 | 5 | 9. Casing: Material <input type="checkbox"/> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <u>10</u> lbs./ft. Dia. <u>15</u> in. to <u>59</u> ft. depth Wall Thickness: inches or Dia. <u>15</u> in. to <u>59</u> ft. depth gage No. <u>15 IN</u> | | |
| BROWN CLAY | | 5 | 8 | 10. Screen: Manufacturer's name <u>JET STREAM</u> Type <u>PVC</u> Dia. <u>18" O.D.</u> Slot/gauze <u>.085</u> Length <u>20</u> ft. Set between <u>39</u> ft. and <u>59</u> ft. ft. and <u>59</u> ft. Gravel pack? <u>YES</u> Size range of material <u>1/4 IN</u> | | |
| GRAY Silty Clay | | 8 | 23 | 11. Static water level: <u>21</u> ft. below land surface Date <u>10-12-77</u> | | |
| FINE SAND WITH GRAY CLAY | | 23 | 36 | 12. Pumping level below land surfaces: ft. after <u> </u> hrs. pumping <u> </u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m. | | |
| MED SAND WITH GRAY CLAY | | 36 | 44 | 13. Water sample submitted: <u>YES</u> No Date <u>10-12-77</u> | | |
| MED COARSE SAND | | 44 | 57 | 14. Well head completion: <u>12</u> Inches above grade | | |
| BLUE SHALE | | 57 | 59 | 15. Well grouted? <u>YES</u> <u>Puddle Clay</u> With: <u>Neat cement</u> <u>Bentonite</u> <u>Concrete</u> Depth: From <u>0</u> ft. to <u>10</u> ft. | | |
| | | | | 16. Nearest source of possible contamination: ft. <u>1000</u> Direction <u>E</u> Type <u>CATTLE</u> Well disinfected upon completion? <u>YES</u> <u>NO</u> | | |
| | | | | 17. Pump: <u>Not installed</u> Manufacturer's name <u>JACK 771</u> Model number <u>6"</u> HP <u>60</u> Volts <u>480</u> Length of drop pipe <u>50</u> ft. capacity <u>200</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | | |
| | | | | 18. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>PETERSON IRRIGATION 138</u> Business name <u>Box 150 LINDSBORG, KS</u> License No. <u> </u> Address <u> </u> Signed <u>Mike Peterson</u> Date <u>10-20-77</u> Authorized representative | | |
| 18. Elevation: | | 19. Remarks: | | | | |
| Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley | | | | | | |

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5