

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well:		County Scott	Fraction 1/4 C 1/4 SE 1/4	Section number 14	Township number T 10 S R 33 #W	Range number																																			
2. Distance and direction from nearest town or city: 9 mi N, 7 mi W of Scott City, Ks. Street address of well location if in city:			3. Owner of well: Isaac Unruh R.R. or street: RR #3 City, state, zip code: Scott City, Ks. 67871																																						
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: C of Qtr.		6. Bore hole dia. 26 in. Completion date _____ Well depth 203 ft. 5/25/76																																					
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Type and color of material</th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr><td>Clay</td><td>0</td><td>20</td></tr> <tr><td>Gyp</td><td>20</td><td>40</td></tr> <tr><td>Sandy clay</td><td>40</td><td>60</td></tr> <tr><td>Gyp</td><td>60</td><td>80</td></tr> <tr><td>Sandy clay</td><td>80</td><td>100</td></tr> <tr><td>Clay, fine sand</td><td>100</td><td>120</td></tr> <tr><td>Fine to med. sand</td><td>120</td><td>140</td></tr> <tr><td>Med/sand, clay bank</td><td>140</td><td>160</td></tr> <tr><td>Med. sand and gravel</td><td>160</td><td>180</td></tr> <tr><td>Med/ sand. c;au, shale at 190</td><td>180</td><td>203</td></tr> <tr><td colspan="3" style="text-align:center;">(Use a second sheet if needed)</td></tr> </tbody> </table>		Type and color of material	From	To	Clay	0	20	Gyp	20	40	Sandy clay	40	60	Gyp	60	80	Sandy clay	80	100	Clay, fine sand	100	120	Fine to med. sand	120	140	Med/sand, clay bank	140	160	Med. sand and gravel	160	180	Med/ sand. c;au, shale at 190	180	203	(Use a second sheet if needed)			7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
		Type and color of material	From	To																																					
		Clay	0	20																																					
		Gyp	20	40																																					
		Sandy clay	40	60																																					
		Gyp	60	80																																					
		Sandy clay	80	100																																					
		Clay, fine sand	100	120																																					
		Fine to med. sand	120	140																																					
		Med/sand, clay bank	140	160																																					
Med. sand and gravel	160	180																																							
Med/ sand. c;au, shale at 190	180	203																																							
(Use a second sheet if needed)																																									
9. Casing: Material Steel Height: Above or below Threaded _____ Welded <input checked="" type="checkbox"/> Surface 12 in. RMP _____ PVC _____ Weight 36.86 lbs./ft. Dia. 16 in. to 203 ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. 219		10. Screen: Manufacturer's name _____ Lakewood Type Millslot Dia. 16" Slot/gauze 1/8x2" Length 58 Set between # 145 ft. and 203 ft. _____ ft. and _____ ft. Gravel pack? Yes Size range of material 1/4"																																							
11. Static water level: _____ mo./day/yr. 145 ft. below land surface Date 5/20/76		12. Pumping level below land surfaces: 197 ft. after 6 hrs. pumping 300 g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield 300 g.p.m.																																							
13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____		14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade																																							
15. Well grouted? Yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		16. Nearest source of possible contamination: NA ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No																																							
17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. High Plains Drilling & Supply, Inc. 136 A Business name License No. _____ Address: 402 N 3rd, Garden City, Ks Signed Bill Harkness Date 6-3-76 Authorized representative																																							
18. Elevation:	19. Remarks:		20. Water well contractor's certification: (continued)																																						
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley																																									

T 10 S R 33 W E 14 CSE 1/4 1/4 1/4