





# Henkle

DRILLING & SUPPLY CO., INC.

3795 W. JONES AVE.  
316/277-2389  
FAX/277-0224

P.O. Box 639  
GARDEN CITY, KANSAS 67846

CUSTOMER'S NAME Loran Jansen DATE July 26, 1990  
 STREET ADDRESS 1301 Elizaebeth TEST # 2 E. LOG Yes  
 CITY & STATE Scott City, Ks. 67871 DRILLER Shelden  
 COUNTY Scott QUARTER SE SECTION 20 TOWNSHIP 16 RANGE 34

LOCATION 100' north of old well

%	FOOTAGE		To	DESCRIPTION OF STRATA	Well location	
	From	Pay			STATIC WATER LEVEL: <u>Approx. 157'</u>	Proposed Well Depth: <u>207'</u>
	0		3	Top soil		
	3		20	Brown silty clay		
	20		26	Light brown clay		
	26		30	Limerock, sand & gravel & some sandy clay mixed		
	30		42	Limerock & some white sandy clay		
	42		55	Limerock cemented sand & some sandy clay		
	55		80	Cemented sand & gravel		
	80		82	Sand fine to medium coarse small to large gravel		
	82		87	Cemented sand & gravel		
	87		99	Brown clay a little sandy cemented sand		
	99		104	Clay		
	104		107	Sand fine to medium coarse small gravel		
	107		112	Sandy clay & sand mixed		
	112		115	Sand fine to medium coarse few small gravel		
	115		118	Sandy clay & some cemented sand		
	118		122	Sand fine to medium coarse		
	122		127	Tannish yellow clay		
	127		157	Sand fine to medium very few coarse cemented streak at 139 (used a little water)		
	157		160	Cemented sand		
	160		169	Tan clay a little sandy		
40	169	9	178	Sand fine to medium & a little sandy clay mixed in		
70	178	14	192	Sand fine to medium coarse small to medium gravel few large (used a little water)		
	192		198	Yellow soap stone		
	198		220	Shale		
				Well depth = 207'		
				2 - bags of Quick Gel		
				1 - Perma Plug		
				1 - bag of Hole Plug		
				Water line 5' or 6' east of test, running north & south		
				Jed A - set up best way		
				Gas line running north & south in the middle of the road		