

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Wichita</b>	Fraction <b>SW 1/4 SE 1/4 SE 1/4</b>	Section number <b>13</b>	Township number <b>T 16 S R 37</b>	Range number <b>EW</b>
2. Distance and direction from nearest town or city: <b>12N, 3/4E</b>				3. Owner of well: <b>Chet Pearson</b>		
Street address of well location if in city: <b>of Leoti, KS</b>				R.R. or street: City, state, zip code: <b>Leoti, KS 67861</b>		
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. <b>26</b> in. Completion date: <b>12-17-74</b> Well depth <b>181</b> ft.	
					7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
					8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
					9. Casing: Material <b>Steel</b> Height: <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>10</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>81.67</b> lbs./ft. Dia. <b>16</b> in. to <b>181</b> ft. depth Wall Thickness: inches or Dia. in. to ft. depth gage No. <b>.188</b>	
5. Type and color of material		From	To	10. Screen: Manufacturer's name <b>Free Flow</b> Type <b>Prime Steel</b> Dia. <b>16 in.</b> Slot gauge <b>.125</b> Length <b>30 ft.</b> Set between <b>151</b> ft. and <b>181</b> ft. ft. and ft. Gravel pack? <b>yes</b> Size range of material <b>3/4-1/2</b>		
Clay		0	22	11. Static water level: mo./day/yr. <b>126</b> ft. below land surface Date <b>10-4-74</b>		
Gyp		22	49	12. Pumping level below land surfaces: <b>151</b> ft. after <b>4</b> hrs. pumping <b>950</b> g.p.m. <b>152</b> ft. after <b>4</b> hrs. pumping <b>990</b> g.p.m. Estimated maximum yield <b>990</b> g.p.m.		
Sd coarse		49	51	13. Water sample submitted: mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date		
Sd rock		51	58	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> inches above grade		
Fine sd clay		58	67	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>15</b> ft.		
Sd coarse		67	77	16. Nearest source of possible contamination: ft. <b>2640</b> Direction <b>W</b> Type <b>Septic</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Clay		77	102	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>Worthington</b> Model number _____ HP _____ Volts _____ Length of drop pipe <b>175</b> ft. capacity <b>990</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Fine sd clay		102	130			
Sd coarse		130	135			
Fine sd clay		135	161			
Sd coarse		161	178			
Clay yellow		178	185			
Shale		185				
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Weishaar Drilling</b> 232 Business name License No. _____ Address <b>Septic City, KS 67871</b> Signed <i>[Signature]</i> 1-17-76 Authorized representative		
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

16  
 320  
 13  
 555555  
 1/4 1/4 1/4  
 Sec

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5