

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Wichita</b>	Fraction <b>SW 1/4 SW 1/4 NE 1/4</b>	Section number <b>25</b>	Township number <b>T 16 S R 38 E</b>	Range number <b>38</b>
2. Distance and direction from nearest town or city: <b>1 1/2 N, 5 1/2 W, 1/2 S of</b>			3. Owner of well: <b>Lorraine McCoy</b>			
Street address of well location if in city: <b>Leoti, KS</b>			R.R. or street: <b>% Louis Willey</b>			
			City, state, zip code: <b>Leoti, KS 67861</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>26</u> in. Completion date <u>6-4-76</u> Well depth <u>203</u> ft.		
				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Clay		0	40	9. Casing: Material <u>Steel</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>10</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>31.67</u> lbs./ft. Dia. <u>16</u> in. to <u>203</u> ft. depth Wall Thickness: inches or Dia. <u>   </u> in. to <u>   </u> ft. depth Igage No. <u>.188</u>		
Gyp		40	52	10. Screen: Manufacturer's name <u>Free Flow</u> Type <u>Prime Steel</u> Dia. <u>16 in.</u> <input checked="" type="checkbox"/> Slotted gauze <u>.125</u> Length <u>50 ft.</u> Set between <u>153</u> ft. and <u>203</u> ft. <u>   </u> ft. and <u>   </u> ft. Gravel pack? <u>yes</u> size range of material <u>3/4 - 1/2</u>		
Clay		52	75	11. Static water level: <u>137</u> ft. below land surface Date <u>3-20-76</u> mo./day/yr.		
Sd coarse		75	80	12. Pumping level below land surfaces: <u>157</u> ft. after <u>4</u> hrs. pumping <u>630</u> g.p.m. <u>160</u> ft. after <u>4</u> hrs. pumping <u>700</u> g.p.m. Estimated maximum yield <u>700</u> g.p.m.		
Clay		80	107	13. Water sample submitted: <u>   </u> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u>   </u>		
Fine sd clay		107	140	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> inches above grade		
Sd rock		140	144	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>15</u> ft.		
Sd coarse		144	160	16. Nearest source of possible contamination: ft. <u>5280</u> Direction <u>SW</u> Type <u>Septic</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Sd rock		160	162	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Western Land Roller</u> Model number <u>GE</u> HP <u>50</u> Vol <u>460</u> Length of drop pipe <u>190</u> ft. capacity <u>700</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Sd coarse		162	172			
Clay		172	177			
Fine sd		177	190			
Sd coarse		190	197			
Fine sd clay		197	200			
Clay yellow		200	203			
Shale	(Use a second sheet if needed)	203	205			
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weishagr Drilling</u> 232 Business name <u>Scott City, KS 67871</u> License No. <u>   </u> Address <u>   </u> Date <u>7-21-76</u> Signed <u>   </u> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

T 16 S 38 E  
 Sec 25  
 1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5