


1 LOCATION OF WATER WELL: County: Wichita Fraction: NE 1/4 NE 1/4 SW 1/4 Section Number: 33 Township Number: T 16 S Range Number: R 38 E/W

Distance and direction from nearest town or city street address of well if located within city?
9 WEST, 9 NORTH 1/2 WEST OF Leoti, KS

2 WATER WELL OWNER: KAN-SUN BEEF, INC. Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: Rt 1 Box 60 Application Number: 17332
 City, State, ZIP Code: Leoti, KS 67861

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:  4 DEPTH OF COMPLETED WELL: 160 ft. ELEVATION: 3400

Depth(s) Groundwater Encountered 1. 127 ft. 2. _____ ft. 3. _____ ft.
 WELL'S STATIC WATER LEVEL 127 ft. below land surface measured on mo/day/yr 4-30-91
 Pump test data: Well water was 160 ft. after 2 hours pumping 225 gpm
 Est. Yield 225 gpm: Well water was _____ ft. after _____ hours pumping _____ gpm
 Bore Hole Diameter: 26 in. to _____ ft., and _____ in. to _____ ft.
 WELL WATER TO BE USED AS:
 5 Public water supply 8 Air conditioning 11 Injection well
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well
 Was a chemical/bacteriological sample submitted to Department? Yes _____ No X; If yes, mo/day/yr sample was submitted _____
 Water Well Disinfected? Yes X No _____

5 TYPE OF BLANK CASING USED:
 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded _____
2 PVC 4 ABS 7 Fiberglass _____ Threaded _____
 Blank casing diameter 12 in. to 120 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.
 Casing height above land surface 12 in., weight _____ lbs./ft. Wall thickness or gauge No. Sch. 40

TYPE OF SCREEN OR PERFORATION MATERIAL:
 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) _____
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE:
 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes
 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) _____

SCREEN-PERFORATED INTERVALS: From 120 ft. to 160 ft., From _____ ft. to _____ ft.
 From _____ ft. to _____ ft., From _____ ft. to _____ ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 160 ft., From _____ ft. to _____ ft.
 From _____ ft. to _____ ft., From _____ ft. to _____ ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other _____
 Grout Intervals: From 5 ft. to 25 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.

What is the nearest source of possible contamination:
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)
 13 Insecticide storage
 Direction from well? SOUTH How many feet? 300

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	TOP SOIL & CLAY	153	160	YELLOW CLAY
10	16	LIMESTONE	160	165	SHALE
16	33	LIMESTONE (HARD)			
33	49	LIMESTONE & SAND (HARD)			
49	61	LIMESTONE & SAND & LITTLE CLAY			
61	71	SAND			
71	72	LIMESTONE (VERY HARD)			
72	82	SANDY CLAY			
82	99	SANDY CLAY & LITTLE Limestone			
99	115	SANDY CLAY			
115	132	SAND (FINE TO MED) 2' Limestone & LITTLE CLAY			
132	145	SAND (FINE)			
145	146	CEMENTED SAND (VERY HARD)			
146	148	SAND & LITTLE CLAY			
148	153	SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5-1-91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 473 This Water Well Record was completed on (mo/day/yr) 5-23-91 under the business name of Tyler Water Well SERVICE by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

0820921006-22