



The  
Professionals

# MINTER-WILSON DRILLING CO.

INCORPORATED

Specialty  
and General  
Water Systems  
Made and  
and Repairing

Phone 276-8269

P.O. Box 493

GARDEN CITY, KANSAS 67816

V. M. Young  
Greeley County  
12-23-75

Location: SE 17-16-39  
13 miles North,  $5\frac{1}{2}$  East from Tribune, from old  
well, 900 feet North, 80 feet West, 3 poles  
North on East side of road going North

Static Water Level: 130'

Test # 1

0	4	Top Soil
4	32	Brown Sandy Clay mixed with Brown Rock
32	40	Brown Sandy Clay mixed with Gravel
40	53	Brown Sandy Clay
53	80	Fine to Med. Sand & Gravel, 10% Clay
80	87	Fine to Med. Sand & Gravel
87	113	Brown Sandy Clay
113	125	Fine to Med. Sand & Gravel (tight)
125	134	Fine to Med. Sand & Gravel (Tight)
134	141	Brown Sandy Clay
141	165	Fine to Med. Sand & Gravel (Little Tight)
165	168	Fine to Med. Sand & Gravel, Clay Streaks
168	186	Fine to Med. Sand & Some Gravel Coarse (Loose)
186	194	Brown Sandy Clay, Gravel Streaks
194	209	Brown Sandy Clay
209	215	Fine to Med. Sand & Gravel
215	227	Med. Sand & Some Coarse Gravel
227	230	Yellow Clay, Shale Mixed

T.O. 237'