

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620



1 Location of well:	County Greeley	Township name	Fraction NW 1/4 NW 1/4 NW 1/4	Section number 17	Town number 16	Range number 40
---------------------	--------------------------	---------------	---	-----------------------------	--------------------------	---------------------------

Distance and direction from nearest town or city: **14N 1W**
Street address of well location if in city: **of Tribune, Kan**

3 Owner of well: **Alfred D. Koehn**
Address: **Tribune, Kansas 67879**

Locate with "X" in section below:

Sketch map:



4 Well depth: **216** ft. Date of completion **May 8, 1977**
Well diameter **12** in.

5 Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

6 Use: Domestic Public supply Industry
 Irrigation Air conditioning Commercial
 Test well

7 Casing: Material **Steel** Height: above/below _____
Threaded Welded Surface **12** in.
Diam. _____ Weight **134** lb./ft.
12 in. to **216** ft. depth Drive shoe? Yes No
_____ in. to _____ ft. depth!

2	Type and color of material	From	To
	soil brown	0	2
	soil yellow	2	15
	clay	15	24
	sand & gravel	24	49
	clay	49	92
	sandy clay	92	132
	clay	132	150
	clay	150	154
	sand	154	155
	clay	155	156
	sand	156	165
	clay white	166	179
	clean sand	179	196
	clay white	196	198
	sand	198	207
	Yellow Clay (use a second sheet if needed)	207	216

8 Screen: Manufacturer **W.A. Brown**
Type **Steel** Dia. **12"**
Slot/gauze **10/30** Length **60'**
Set between **156** ft. and **216** ft.
Fittings:
Gravel pack Yes No Size range of material **21"**

9. Static water level:
150 ft. below land surface Date **May 8, 1977**

10 Pumping level below land surfaces:
~~_____~~ ft. after _____ hrs. pumping _____ g.p.m.
_____ ft. after _____ hrs. pumping _____ g.p.m.
Estimated maximum yield **650** g.p.m.

11 Water sample submitted:
 Yes No Date _____

12 Well head completion:
 Pitless adapter Inches above grade

13 Well grouted? Yes No
 Neat cement Bentonite _____
Depth: From **2** ft. to **10** ft.

14 Nearest source of possible contamination:
ft. _____ Direction _____ Type _____
Well disinfected upon completion? Yes No

15 Pump: Not installed
Manufacturer's name **Valley**
Model number _____ HP _____ Volts _____
Length of drop pipe **202** ft. capacity **600** g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

16 Remarks: elevation

Topography:
 Hill
 Slope
 Upland
 Valley

17 Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Whinery Drilling 256
Business name License No. _____
Address **405 Antelope St. Scott City,**
Signed **John Whinery** Date **7-22-70**
Authorized representative

16 40 W 17 N NW 1/4