

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment (Water well Contractors) Topeka, Kansas 66620

Location of well:	County <b>Greeley</b>	Fraction <b>NW 1/4 SE 1/4 SE 1/4</b>	Section number <b>17</b>	Township number <b>T 16 S R 40 E/W</b>	Range number <b>40</b>
-------------------	--------------------------	---	-----------------------------	---	---------------------------

Distance and direction from nearest town or city: **13 mi. north of Tribune**

Street address of well location if in city:

3. Owner of well: **Steele Farms**

R.R. or street:

City, state, zip code: **Tribune, Kans. 67879**

4. Locate with "X" in section below:

Sketch map:

1 Mile

1 Mile

6. Bore hole dia. 26 in. Completion date 12-20-75  
Well depth 215 ft.

7.  Cable tool  Rotary  Driven  Dug  
 Hollow rod  Jetted  Bored  Reverse rotary

8. Use:  Domestic  Public supply  Industry  
 Irrigation  Air conditioning  Stock  
 Lawn  Oil field water  Other

9. Casing: Material steel Height: Above or below SSW  
Threaded  Welded  Surface 12 in.  
RMP  PVC  Weight 40 lbs./ft.  
Dia. 16 in. to 165 ft. depth Wall Thickness: inches or  
Dia.     in. to     ft. depth gage No. 219

5. Type and color of material	From	To
Overburden	0	140
Sand	140	170
Clay	170	174
Sand & Sandy clay	174	186
Clay	186	190
Cemented sand & sand streaked	190	211
Clay	211	215
Shale	215	
(Use a second sheet if needed)		

10. Screen: Manufacturer's name W. A. Brown  
Type Free Floe Dia. 16"  
Slot/gauze slot Length 50 ft.  
Set between 165 ft. and 215 ft.  
    ft. and     ft.  
Gravel pack?  Size range of material 5/8

11. Static water level: 150 ft. below land surface Date 12-22-75 mo./day/yr.

12. Pumping level below land surfaces:  
190 ft. after 4 hrs. pumping 450 g.p.m.  
    ft. after     hrs. pumping     g.p.m.  
Estimated maximum yield 450 g.p.m.

13. Water sample submitted:     mo./day/yr.  
Yes  No  Date    

14. Well head completion:  
    Pitless adapter 18 Inches above grade

15. Well grouted? yes  
With:     Neat cement     Bentonite  Concrete  
Depth: From 0 ft. to 10 ft.

16. Nearest source of possible contamination:  
ft.     Direction     Type None  
Well disinfected upon completion?     Yes  No

17. Pump:  Not installed  
Manufacturer's name      
Model number     HP     Volts      
Length of drop pipe     ft. capacity     g.p.m.  
Type:  
 Submersible  Turbine  
 Jet  Reciprocating  
 Centrifugal  Other

18. Elevation:

Topography:  
 Hill  
 Slope  
 Upland  
 Valley

19. Remarks:  
**Ground is level**

20. Water well contractor's certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

**ARK VALLEY PUMP & SUPPLY 123**  
Business name License No.      
Address Box 235 Holly, Colo.  
Signed Dave Smith 1-2-76  
Authorized Representative

T 16 R 40 S 17 NE 1/4 SE