


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County <u>Saline</u>	Township name	Fraction <u>SE NW</u>	Section number <u>27</u>	Town number <u>165</u>	Range number <u>5W</u>
Distance and direction from nearest town or city: <u>2 1/2 Mi. S. of Falun</u>			3 Owner of well: <u>Lewis Franklin</u> Address: <u>1828 Simmons</u> <u>Salina Kans</u>			
Street address of well location if in city:						
Locate with "X" in section below: N  W S E 1 Mile			Sketch map:			
2			Type and color of material			From To
Clay + silt, gray + buff			0			9
Muniescah sh:						
Shale, silty red + gray			9			40.5
Dolomite, silty, white + greenish-gray			40.5			41
contains celestite vugs						
Shale, red + gray			41			47
Shale, dark blue-gray (Poss. top Wellington)			47			50
(use a second sheet if needed)						
16 Remarks: elevation						
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						
			4 Well depth: <u>50</u> ft. Date of completion: <u>3-22-75</u> Well diameter <u>4"</u> in.			
			5 <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
			6 Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well <input type="checkbox"/>			
			7 Casing: Material <u>PVC</u> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. Diam. <u>4</u> in. to <u>50</u> ft. depth Drive shoe? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <u>4</u> in. to <u>50</u> ft. depth			
			8 Screen: Manufacturer <u>slotted</u> Type <u>PVC</u> Dia. <u>4"</u> Slot/gauze <u>3/32"</u> Length <u>3'</u> Set between <u>47</u> ft. and <u>50</u> ft. Fittings: Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>M</u>			
			9 Static water level: <u>7.7</u> ft. below land surface Date <u>3-22-75</u>			
			10 Pumping level below land surfaces: <u>35</u> ft. after <u>1</u> hrs. pumping <u>5</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>7</u> g.p.m.			
			11 Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>			
			12 Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade			
			13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Depth: From <u>3</u> ft. to <u>13</u> ft.			
			14 Nearest source of possible contamination: ft. <u>12</u> Direction <u>5</u> Type <u>Dug well</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
			15 Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.m.p. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Hydraulic Drilling</u> <u>126</u> Business name License No. Address <u>At 2 Salina</u> Signed <u>Art Fent</u> Date <u>3-27-75</u> Authorized representative			