

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

20070091

1 LOCATION OF WATER WELL: County: Barton Fraction SE 1/4 SE 1/4 NW 1/4 Section Number 15 Township Number T 17 S Range Number R 13W E/W

Distance and direction from nearest town or city street address of well if located within city? N, 1E of Hoisington, KS Global Positioning Systems (decimal degrees, min. of 4 digits) Latitude: Longitude: Elevation: Datum: Data Collection Method:

2 WATER WELL OWNER: Mike Demel RR#, St. Address, Box #: 1109 N. Green City, State, ZIP Code: Hoisington, KS 67544

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: [Diagram showing a 2x2 grid with 'X' in the top-left quadrant] 4 DEPTH OF COMPLETED WELL: 74 ft. Depth(s) Groundwater Encountered: 24 ft. WELL'S STATIC WATER LEVEL: 24 ft. below land surface measured on 03/15/07

5 TYPE OF CASING USED: 1 Steel, 3 RMP (SR), 6 Asbestos-Cement, 9 Other (specify below), 2 PVC, 4 ABS, 7 Fiberglass, 8 Concrete tile, CASING JOINTS: Glued, Clamped, Welded, Threaded. Blank casing diameter: 5 in. to 20 ft., Diameter. Casing height above land surface: 12 in., Weight: 2.8 lbs./ft. Wall thickness or gauge No. Sch. 40

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel, 3 Stainless Steel, 5 Fiberglass, 7 PVC, 9 ABS, 11 Other (Specify). SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot, 3 Mill slot, 5 Gauzed wrapped, 7 Torch cut, 9 Drilled holes, 11 None (open hole). SCREEN-PERFORATED INTERVALS: From 20 ft. to 74 ft. GRAVEL PACK INTERVALS: From 20 ft. to 74 ft.

6 GROUT MATERIAL: 1 Neat cement, 2 Cement grout, 3 Bentonite, 4 Other. Grout Intervals: From 0 ft. to 20 ft. What is the nearest source of possible contamination: 1 Septic tank, 4 Lateral lines, 7 Pit privy, 10 Livestock pens, 13 Insecticide Storage, 16 Other (specify below)

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows include: 0 to 2 top soil, 2 to 10 clay, 10 to 24 shale, 24 to 26 broken sand rock, 26 to 74 shale with sand rock streaks. Plugging intervals: Demel #1-15, Sterling Drilling Company, P. O. Box 1006, Pratt, KS 67124

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 03/15/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 186 This Water Well Record was completed on (mo/day/year) 04/02/07 under the business name of Kelly's Water Well Services, Inc. by (signature)

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html.