

WATER WELL RECORD

Form WWC-5

Well #1
Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Barton, Fraction 1/4 SE 1/4 SE 1/4 SW 1/4, Section Number 28, Township No. T 17 S, Range Number R 14, Global Positioning System (GPS) information: Latitude, Longitude, Elevation, Datum, Collection Method.

2 WATER WELL OWNER: Thomas Larsen, RR#, Street Address, Box #: 562 W State Road 4, City, State, ZIP Code : Olmitz. KS 67564
3 LOCATE WELL WITH AN "X" IN SECTION BOX: [Diagram showing a 4-section grid with 'X' in the SE section]
4 DEPTH OF COMPLETED WELL 80 ft. Depth(s) Groundwater Encountered (1) 47 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 47 ft. below land surface measured on mo/day/yr. 6-26-13. Pump test data: Well water was ft. after hours pumping gpm. EST. YIELD N/A gpm. Well water was ft. after hours pumping gpm. Bore Hole Diameter 10 in. to 80 ft., and in. to ft. WELL WATER TO BE USED AS: [Checked] Domestic, [] Feedlot, [] Oil field water supply, [] Dewatering, [] Other (Specify below), [] Irrigation, [] Industrial, [] Domestic-lawn & garden, [] Monitoring well. Was a chemical/bacteriological sample submitted to Department? [] Yes [Checked] No. If yes, mo/day/yr sample was submitted. Water well disinfected? [Checked] Yes [] No.

5 TYPE OF CASING USED: [] Steel [Checked] PVC [] Other
CASING JOINTS: [Checked] Glued [] Clamped [] Welded [] Threaded
Casing diameter .5 in. to 80 ft., Diameter in. to ft., Diameter in. to ft.
Casing height above land surface 18 in., Weight SDR-26 lbs./ft., Wall thickness or gauge No.
TYPE OF SCREEN OR PERFORATION MATERIAL: [] Steel [] Stainless Steel [Checked] PVC [] Other (Specify)
[] Brass [] Galvanized Steel [] None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE: [] Continuous slot [] Mill slot [] Gauze wrapped [] Torch cut [] Drilled holes [] None (open hole)
[] Louvered shutter [] Key punched [] Wire wrapped [Checked] Saw cut [] Other (specify)
SCREEN-PERFORATED INTERVALS: From 80 ft. to 50 ft., From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From 80 ft. to 20 ft., From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: [] Neat cement [] Cement grout [Checked] Bentonite [] Other
Grout Intervals: From ft. to ft., From 20 ft. to 0 ft., From ft. to ft.
What is the nearest source of possible contamination: [] Septic tank [] Lateral lines [] Pit privy [] Livestock pens [] Insecticide storage [Checked] Other (specify below)
[] Sewer lines [] Cesspool [] Sewage lagoon [] Fuel storage [] Abandoned water well
[] Watertight sewer lines [] Seepage pit [] Feedyard [] Fertilizer storage [] Oil well/gas well [] None
Direction from well Distance from well

Table with 6 columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, LITHO. LOG (cont.) or PLUGGING INTERVALS. Rows include: 0-4 Top soil, 4-14 Brown clay, 14-22 Light gray shale, 22-28 Yellow & gray shale/ sandstone/ ironated rock, 28-54 Light gray shale/ sandstone streaks, 54-80 Sandstone/ shale streaks.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was [Checked] constructed, [] reconstructed, or [] plugged under my jurisdiction and was completed on (mo/day/year) 9-3-13 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134. This Water Well Record was completed on (mo/day/year) 9-12-13 under the business name of Rosencrantz Bemis Ent Inc by (signature) [Signature]

INSTRUCTIONS: Use tyewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. I include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html.