


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Lane	Fraction NW 1/4 NW 1/4 NW 1/4	Section number 5	Township number T 17 S R 30	Range number 30
2. Distance and direction from nearest town or city: 8N, 14E, 1N, 1W, Street address of well location if in city: 1/2 S of Scott City, KS			3. Owner of well: Kenneth Wilkens R.R. or street: 545 S. Delaware Delaware City, state, zip code: Dighton, KS 67839			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. 26 in. Completion date 3-11-76 Well depth 175 ft.		
5. Type and color of material		From	To	7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Clay		0	21	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Gyp		21	40	9. Casing: Material Steel Height Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 10 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 31.67 lbs./ft. Dia. 16 in. to 175 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gauge No. 188		
Sd rock H		40	53	10. Screen: Manufacturer's name Johnson Galv. & Prime & Free Flow Type Steel Dia. 16 in. Slot gauge 100 & 125 Length 30 ft. Set between 145 ft. and 175 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? yes Size range of material 3/4-1		
Fine sd clay		53	62	11. Static water level: 111 ft. below land surface Date 1-30-76 mo./day/yr.		
Sd rock H		62	82	12. Pumping level below land surfaces: 153 ft. after 4 hrs. pumping 435 g.p.m. 162 ft. after 4 hrs. pumping 470 g.p.m. Estimated maximum yield 470 g.p.m.		
Fine sd clay		82	88	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> mo./day/yr.		
Sd rock H		88	95	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> inches above grade		
Fine sd clay T		95	106	<input checked="" type="checkbox"/> Well grouted? <input type="checkbox"/> With: <input checked="" type="checkbox"/> cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 15 ft.		
Fine sd clay		106	120	16. Nearest source of possible contamination: ft. 2640 Direction SW Type Septic Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
Fine sd		120	138	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Western Land Roller Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe 165 ft. capacity 470 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
Fine sd clay		138	142	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weishaar Drilling 232 Business name License No. Address Scott City, KS 67871 Signature [Signature] Authorized Representative 7-21-76		
Fine sd		142	147			
Fine sd clay		147	157			
Sd coarse		157	169			
Fine sd		169	172			
Yellow (Use a second sheet if needed)		172	178			
18. Elevation:		19. Remarks: Shale				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5