

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Lane</u>	Fraction <u>SW 1/4 NW 1/4 SW 1/4</u>	Section number <u>9</u>	Township number <u>T 17 S</u>	Range number <u>R 30 E/W</u>
2. Distance and direction from nearest town or city: <u>2 W .75 S</u> Street address of well location if in city: <u>of Healy Ks</u> <u>E of road N of Mo RR.</u>			3. Owner of well: <u>Dale Graves</u> R.R. or street: <u>Healy, Kansas</u> City, state, zip code: <u>Healy, Kansas</u>			
4. Locate with "X" in section below:		Sketch map:			6. Bore hole dia. <u>20</u> in. Completion date <u>9-24-76</u> Well depth <u>175</u> ft.	
					7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
5. Type and color of material		From	To	9. Casing: Material <u>Steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>135</u> lbs./ft. Dia. <u>12</u> in. to <u>175</u> ft. depth Wall Thickness: inches or Dia. <u>12</u> in. to <u>175</u> ft. depth gage No. <u>134</u>		
<u>Soil</u>		<u>0</u>	<u>10</u>	10. Screen: Manufacturer's name <u>W.A. Brown</u>		
<u>clay rock & sand</u>		<u>10</u>	<u>90</u>	Type <u>Steel</u> Dia. <u>12 3/4</u>		
<u>sandy clay</u>		<u>90</u>	<u>105</u>	Slot/gauze <u>10/20</u> Length <u>40</u>		
<u>clay Fine sand</u>		<u>110</u>	<u>113</u>	Set between <u>135</u> ft. and <u>175</u> ft.		
<u>clay Fine sand</u>		<u>113</u>	<u>117</u>	ft. and <u>175</u> ft.		
<u>clay</u>		<u>117</u>	<u>119</u>	Gravel pack? ☒ Size range of material <u>3"-1"</u>		
<u>sand</u>		<u>119</u>	<u>120</u>	11. Static water level: <u>105</u> ft. below land surface Date <u>9-24-76</u>		
<u>fine sand & clay</u>		<u>120</u>	<u>126</u>	12. Pumping level below land surfaces:		
<u>fine sand</u>		<u>126</u>	<u>135</u>	ft. after <u>0</u> hrs. pumping <u>0</u> g.p.m.		
<u>fine sand & clay</u>		<u>135</u>	<u>150</u>	ft. after <u>0</u> hrs. pumping <u>0</u> g.p.m.		
<u>fine sand with clay</u>		<u>150</u>	<u>157</u>	Estimated maximum yield <u>400</u> g.p.m.		
<u>Good sand & gravel</u>		<u>157</u>	<u>167</u>	13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>9-24-76</u>		
<u>Yellow clay</u>		<u>167</u>	<u>170</u>	14. Well head completion:		
<u>Blue Shale</u>		<u>170</u>	<u>175</u>	☐ Pitless adapter <u>0</u> inches above grade		
(Use a second sheet if needed)				15. Well grouted? ☒ YES		
				With: <u>Neat cement</u> ☒ Bentonite ☐ Concrete		
				Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination:		
				ft. <u>60</u> Direction <u>W</u> Type <u>Road ditch</u>		
				Well disinfected upon completion? ☐ Yes ☐ No		
				17. Pump:		
				Not installed		
				Manufacturer's name <u>Valley</u>		
				Model number <u>D110</u> HP <u>1</u> Volts <u>115</u>		
				Length of drop pipe <u>165</u> ft. capacity <u>400</u> g.p.m.		
				Type:		
				☐ Submersible ☒ Turbine		
				☐ Jet ☐ Reciprocating		
				☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography:				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
☐ Hill				<u>WHITNEY DRILLING 256</u>		
☒ Slope				Business name <u>405 Antelope Scott City, Mo</u>		
☐ Upland				Address <u>405 Antelope Scott City, Mo</u>		
☐ Valley				Signed <u>J. L. Whitner</u> Date <u>9-30-76</u>		
				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5