

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
 COUNTY: 086 SCOTT : NW 1/4 SW 1/4 NW 1/4 : 16 : T 17 S : R 34 W

Distance and direction from nearest town or city street address of well if located within city?
 APPX 1/2 EAST, 5 1/2 NORTH, 1 WEST & 3/4 NORTH OF SCOTT CITY

2 WATER WELL OWNER: DECKER BROTHERS
 RR#, St. Address, Box # : 10331 W ROAD 215 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SCOTT CITY, KS 67871- Application Number: 25,097

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 209 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 135 ft. below land surface measured on mo/day/yr 01/05/98
 Pump testdata: Well water was 200 ft. after 3 hours pumping 50 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 209 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 209 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 145 ft. to 155 ft., From 165 ft. to 175 ft.
 From 155 ft. to 165 ft., From 189 ft. to 199 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 209 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHWEST How many feet? 198

| FROM | TO | LITHOLOGIC LOG | FROM | TO | PLUGGING INTERVALS |
|------|-----|-----------------------------|------|----|--------------------|
| 0 | 1 | 02 SILT | | | |
| 1 | 21 | 01 CLAY | | | |
| 21 | 41 | 36 GYP ROCK 01 CLAY | | | |
| 41 | 71 | 36 GYP ROCK 05 SAND | | | |
| 71 | 81 | 01 CLAY 36 GYP ROCK | | | |
| 81 | 95 | 01 CLAY | | | |
| 95 | 102 | 07 FINE SAND 01 CLAY | | | |
| 102 | 105 | 01 CLAY | | | |
| 105 | 120 | 07 FINE SAND 08 MEDIUM SAND | | | |
| 120 | 130 | 01 CLAY | | | |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/02/98 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/22/98
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

| | | | | |
|---------------------------|----------------------|----------------|-----------------|--------------|
| 1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number |
| COUNTY: 086 SCOTT | NW 1/4 SW 1/4 NW 1/4 | 16 | T 17 S | R 34 W |

| | | |
|---------------------------|------------------|---|
| 2 WATER WELL OWNER: | DECKER BROTHERS | Board of Agriculture, Division of Water Resources |
| RR#, St. Address, Box # : | 10331 W ROAD 215 | |

| | | |
|-------------------------|-----------------------|----------------------------|
| City, State, ZIP code : | SCOTT CITY, KS 67871- | Application Number: 25,097 |
|-------------------------|-----------------------|----------------------------|

| FROM | TO | LITHOLOGIC LOG |
|------|-----|--|
| 130 | 152 | 07 FINE SAND 01 CLAY |
| 152 | 162 | 04 SANDY CLAY |
| 162 | 175 | 07 FINE SAND 08 MEDIUM SAND 01 CLAY |
| 175 | 191 | 01 CLAY |
| 191 | 199 | 08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL |
| 199 | 203 | 31 CALICHE |
| 203 | 0 | 19 SHALE |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/02/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/22/98 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce Richmuth*