


RUSSELL SPRINGS 35W

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

CAC

1. Location of well:		County Wichita	Fraction SW 1/4 NE 1/4 SW 1/4	Section number 20	Township number T 17 S R	Range number 39-E/W
2. Distance and direction from nearest town or city: 5 north, 3 1/2 west Street address of well location if in city: of Leoti, Ks.			3. Owner of well: Tim Jaeger R.R. or street: City, state, zip code: Leoti, Ks.			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		6. Bore hole dia. 26 in. Completion date 5-1-75 Well depth 488 ft.	
5. Type and color of material			From		To	
			BRICK 184'			
		10. Screen: Manufacturer's name Johnson Division Type Galv. Dia. 16" Slot 80 Length 20' Set between 160 ft. and 180 ft. Perf: 120-160 and 180-188 ft. Gravel pack? yes Size range of material 1/2" down		11. Static water level: 106 ft. below land surface Date 4-30-75 mo./day/yr.		
		12. Pumping level below land surfaces: 157 ft. after 2 hrs. pumping 645 g.p.m. air ft. after _____ hrs. pumping 690 g.p.m. Estimated maximum yield 650 g.p.m.		13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____		
		14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade		15. Well grouted? yes With: <input checked="" type="checkbox"/> Neat cement _____ Bentonite _____ Concrete _____ Depth: From 0 ft. to 10 ft.		
		16. Nearest source of possible contamination: N/A ft. _____ Direction _____ Type _____ Well disinfected upon completion? _____ Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		17. Pump: Not installed Manufacturer's name Peerless - FMC Model number 5133 HP 75 Volts _____ Length of drop pipe 175 ft. capacity 600 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks: 3346 (TOPO)		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. 208 Minter-Wilson Drilling Co., Inc. Business name License No. _____ Address Box 493 Garden City, Ks. Signed [Signature] Date 11-13-74 Authorized representative		

L 2 39 20 SW NE 35W

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

TIM JAEGER
Wichita County
4-11-75

Test #3

Location: in corner SW on 1/2 mile line SW 1/4 20-17-~~36~~ 37

Static: 130' ?

0	1	Top soil
1	25	Brown clay
25	44	Brown sandy with rock
44	60	Fine to medium sand & gravel (loose)
60	71	Medium coarse gravel (loose)
71	76	Brown sandy clay
76	86	Fine sand (loose)
86	115	Brown sandy clay - streaks of gravel (tight)
115	141	Fine to medium sand & gravel (tight)
141	146	Brown sandy clay
146	155	Fine to medium sand & gravel (loose)
155	181	Fine to medium sand 15% clay
181	184	Fine to medium sand & gravel (loose)
184	185	Yellow clay

T.D. 188 XXX

20' Screen