

Cap - Ob

1 LOCATION OF WATER WELL: County: Ellsworth		Fraction SE 1/4 SE 1/4 SE 1/4	Section Number 32	Township Number T 17 S	Range Number R 9 NW
Distance and direction from nearest town or city street address of well if located within city? 2 East, 1/2 North, 1/2 East of Bushton					
2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP Code :		Hydrocarbon Transportation Inc. Box 5-L Bushton, Kansas 67427			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 105 ft. ELEVATION: NA Depth(s) Groundwater Encountered 1 ft. 2. NA ft. 3. NA ft. WELL'S STATIC WATER LEVEL 42 ft. below land surface measured on mo/day/yr 8/13/1982 Pump test data: Well water was NA ft. after NA hours pumping NA gpm Est. Yield NA gpm: Well water was NA ft. after NA hours pumping NA gpm Bore Hole Diameter 10 in. to NA ft. and NA in. to NA ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only X Observation well Was a chemical/bacteriological sample submitted to Department? Yes X No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No X			
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped X X PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded X Blank casing diameter 4 in. to 72 ft., Dia 4 in. to 100 ft., Dia NA in. to NA ft. Casing height above land surface 36 in., weight 2.81 lbs./ft. Wall thickness or gauge No. Schedule 80 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) X SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped X Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) X SCREEN-PERFORATED INTERVALS: From 72 ft. to 78 ft., From 100 ft. to 105 ft. GRAVEL PACK INTERVALS: From 4 ft. to 105 ft., From NA ft. to NA ft.					
6 GROUT MATERIAL: X 1 Neat cement 2 Cement grout 3 Bentonite 4 Other X Grout Intervals: From 0 ft. to 4 ft., From NA ft. to NA ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) Direction from well? West How many feet? 2300 Storage wells in area					
FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG			
0	4	topsoil			
4	28	brown clay			
28	69	brown clay (soft)			
69	78	gray clay			
78	93	sandrock w/ clay layers			(P-34)
93	100	sandrock			
100	105	blue clay			
105		stop			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was X constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8/3/1982 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 359 This Water Well Record was completed on (mo/day/yr) 8/26/1982 under the business name of Daryl Cox & Sons Inc. by (signature) Daryl Cox INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

EW

SEC. 32

SE 1/4

SE 1/4

SE 1/4

SE 1/4

SE 1/4

SE 1/4

SE 1/4

SE 1/4

SE 1/4

SE 1/4