

1 LOCATION OF WATER WELL: County: Barton Fraction SE 1/4 NE 1/4 SE 1/4 Section Number 5 Township Number 18 Range Number 13

Distance and direction from nearest town or city street address of well if located within city? NE corner of Walnut and Railroad St., Hoisington, KS

2 WATER WELL OWNER: Collingwood Grain P.O. Box 2150 Hoisington, Kansas 67544 Board of Agriculture, Division of Water Resources Application Number: 1830.4

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: [Diagram showing a 36-section grid with the SE section marked with an 'X']

4 DEPTH OF COMPLETED WELL: 25 ft. ELEVATION: 1830.4 ft. WELL'S STATIC WATER LEVEL: 16.1 ft. below land surface measured on 1/9/95 Pump test data: Well water was NA ft. after NA hours pumping Est. Yield NA gpm Well water was 25 ft. after 25 hours pumping Bore Hole Diameter: 8 in. to 25 ft. and 10 in. to 10 ft.

5 TYPE OF BLANK CASING USED: 1 Steel 2 PVC 3 RMP (SR) 4 ABS 5 Wrought iron 6 Asbestos-Cement 7 Fiberglass 8 Concrete tile 9 Other (specify below) CASING JOINTS: Glued Clamped Welded Threaded

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 2 Brass 3 Stainless steel 4 Galvanized steel 5 Fiberglass 6 Concrete tile 7 Gauzed wrapped 8 RMP (SR) 9 ABS 10 Asbestos-cement 11 Other (specify) 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 2 Louvered shutter 3 Mill slot 4 Key punched 5 Wire wrapped 6 Torch cut 7 Saw cut 8 Drilled holes 9 Other (specify) 10 None (open hole)

SCREEN-PERFORATED INTERVALS: From 10 ft. to 25 ft. GRAVEL PACK INTERVALS: From 8 ft. to 25 ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout intervals: From 0 ft. to 6 ft. From 6 ft. to 8 ft.

What is the nearest source of possible contamination: 1 Septic tank 2 Sewer lines 3 Watertight sewer lines 4 Lateral lines 5 Cess pool 6 Seepage pit 7 Pit privy 8 Sewage lagoon 9 Feedyard 10 Livestock pens 11 Fuel storage 12 Fertilizer storage 13 Insecticide storage 14 Abandoned water well 15 Oil well/Gas well 16 Other (specify below) Fuel Storage

Direction from well? How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	Clay, Dark Brown			MW4
1	3	Clay, Very Dark Gray			GeoCore # 114125 Flush-mount Cover
3	10	Clay, Medium Red Brown			# 06005293 Tag # 110167
10	14	Clay, Light Orange Brown			
14	25	Clay, Light Gray			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 1/9/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 2/9/95 under the business name of GeoCore Services, Inc. by (signature) Dale Rold

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.