

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Barton</u>	Fraction <u>1/4 C 1/4 NE 1/4</u>	Section number <u>30</u>	Township number <u>T 18 S</u>	Range number <u>R 14 E</u>
2. Distance and direction from nearest town or city: <u>12-11 5 3/4 - E of Albert, Ks.</u>				3. Owner of well: <u>Don Baker</u> R.R. or street: <u>Timber, Ks. 67582</u> City, state, zip code: <u>Timber, Ks. 67582</u>		
4. Locate with "X" in section below: N W E S 1 Mile				Sketch map: <u>These directions should be right</u>		
5. Type and color of material				From	To	6. Bore hole dia. <u>27</u> in. Completion date <u>12-19-75</u> Well depth <u>110</u> ft.
<u>top soil</u>				<u>0</u>	<u>3</u>	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
<u>clay</u>				<u>3</u>	<u>27</u>	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
<u>sand w/ clay streaks</u>				<u>27</u>	<u>44</u>	9. Casing: Material <u>Steel</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>18</u> in. RMP ☐ PVC ☐ Weight <u>16</u> lbs./ft. Dia. <u>16</u> in. to <u>110</u> ft. depth Wall Thickness: inches or Dia. <u>16</u> in. to <u>110</u> ft. depth gage No. <u>7</u>
<u>clay</u>				<u>44</u>	<u>48</u>	10. Screen: Manufacturer's name <u>Bennet</u> Type <u>slotted</u> Dia. <u>16</u> Slot/gauge <u>3/16</u> Length <u>60</u> Set between <u>50</u> ft. and <u>110</u> ft. ft. and <u>110</u> ft. Gravel pack? ☒ Size range of material <u>2/4-3/8-1/2</u>
<u>Good sand + gravel</u>				<u>48</u>	<u>53</u>	11. Static water level: <u>14</u> ft. below land surface Date <u>2-7-75</u> mo./day/yr.
<u>clay</u>				<u>53</u>	<u>55</u>	12. Pumping level below land surfaces: <u>19</u> ft. after <u>1</u> hrs. pumping <u>100</u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1000</u> g.p.m.
<u>Good gravel</u>				<u>55</u>	<u>63</u>	13. Water sample submitted: <u>Yes</u> No Date <u>2-10-75</u> mo./day/yr.
<u>sand + gravel w/ clay</u>				<u>63</u>	<u>69</u>	14. Well head completion: ☐ Pitless adapter <u> </u> inches above grade
<u>clay, sand streaks</u>				<u>69</u>	<u>74</u>	15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
<u>clay</u>				<u>74</u>	<u>75</u>	16. Nearest source of possible contamination: ft. <u>4</u> mi. Direction <u>SW</u> Type <u>oil well</u> Well disinfected upon completion? ☒ Yes ☐ No
<u>Good sand + gravel</u>				<u>75</u>	<u>83</u>	17. Pump: Not installed Manufacturer's name <u>W.S.R.</u> Model number <u>1-12314</u> HP <u>20</u> Volts <u>460</u> Length of drop pipe <u>100</u> ft. capacity <u>1000</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
<u>clay</u>				<u>83</u>	<u>84</u>	
<u>Good sand + gravel</u>				<u>84</u>	<u>98</u>	
<u>clay</u>				<u>98</u>	<u>101</u>	
<u>sand + gravel</u>				<u>101</u>	<u>103</u>	
<u>clay</u>				<u>103</u>	<u>104</u>	
<u>sand + gravel</u> (Use a second sheet if needed)				<u>104</u>	<u>105</u>	
18. Elevation: <u>1918'</u> Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley		19. Remarks: <u>fire clay</u>		<u>105</u>	<u>110</u>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosenberry, Benis 134</u> Business name <u>Great Bend, Ks</u> license No. <u> </u> Address <u> </u> Signed <u>S. Kilgore</u> Date <u>6-19-75</u> Authorized representative