


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Barton	Fraction NE 1/4 NE 1/4 SE 1/4	Section number 35	Township number T 18 S R 14 E W	Range number 14
2. Distance and direction from nearest town or city: 6 miles Northwest of Great Bend, KS Street address of well location if in city:				3. Owner of well: William Stoss, Jr. R.R. or street: Route 1 City, state, zip code: Great Bend, KS 67530		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>24</u> in. Completion date <u>7-11-77</u> Well depth <u>124</u> ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil		0	3	9. Casing: Material <u>Steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>3.03</u> lbs./ft. Dia. <u>16</u> in. to <u>84</u> ft. depth Wall Thickness: inches or Dia. <u>16</u> in. to <u>84</u> ft. depth gage No. <u>7</u> ga.		
Brown & gray clay		3	55	10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Double-slot</u> Dia. <u>16"</u> ☒ gauze <u>1/8</u> Length <u>40'</u> Set between <u>84</u> ft. and <u>124</u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u>		
Blue & gray clay		55	80	11. Static water level: <u>41' 6"</u> ft. below land surface Date <u>6-8-77</u> mo./day/yr.		
Sand & gravel & thin clay streaks at 87'		80	107	12. Pumping level below land surfaces: <u>N/C</u> ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.		
Sand & gravel & clay streaks		107	113	13. Water sample submitted: ____ mo./day/yr. ____ Yes ☒ No Date ____		
Sand & gravel		113	123	14. Well head completion: ____ Pitless adapter <u>12</u> inches above grade		
Dakota clay		123	124	15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: <u>FIELD</u> ft. ____ Direction ____ Type ____ Well disinfected upon completion? ____ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name <u>Peerless Pump</u> Model number <u>12MB-2</u> HP <u>40</u> Volts <u>460</u> Length of drop pipe <u>90</u> ft. capacity <u>900</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Clarke Well & Eq., Inc.</u> <u>185</u> Business name License No. Address <u>Great Bend, KS 67530</u> Signed <u>[Signature]</u> Date <u>7-15-77</u> Authorized representative		
18. Elevation: <u>1891</u> Topography: <u>TH</u> ☐ Hill ☐ Slope ☐ Upland ☐ Valley		19. Remarks:				